

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>50</u> N. <u>W.</u> , R. <u>34</u> <u>W.</u>	E5
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. _____ S. _____ R. _____ E. _____ W. _____	
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ S. _____ R. _____ E. _____ W. _____	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19\_\_\_\_, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Sec. Corner 8, 9, 16, & 17, T50N, R34W:

Hemlock post	(Not found.	No subsequent monuments found.)
Hemlock 12 N60W 8	(Not found. "	accessories found.)
Maple 8 S41E 45	(Not found. "	" " " " )

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Re-established 11/3/75 at intersection of the N'y extension of a line between a sec. cor. 1 mile S and a 1/4 cor. 1/2 mile S, and the W'y extension of a line between a sec. cor. 1 mile E and a 1/4 cor. 1/2 mile E. The direction of these lines is based on original line tree and corner evidence, and as my experience based on retracing some 2 miles of lines in this twp. has shown direction and not distances to be the most reliable guide to original corner placement, I believe this method is the most satisfactory to use in restoring this corner nearest to its original location.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1" I.D. x 36" iron pipe with 3 3/4" aluminum cap.

Red Oak 12 S77°E (mag.) 24.0 ft. "S16, NBT"  
 Red Oak 12 N54°W (mag.) 5.4 ft. "S 8, NBT"

Note: Distances are measured horizontally.

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Arthur O. Enger DATE October 21, 1976  
CHIEF OF SURVEY PARTY  
MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger  
 Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

