

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>50</u> N. <u>X</u> , R. <u>34</u> W.	E7 & E8
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. _____ S., R. _____ E. _____ W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ S., R. _____ E. _____ W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on see below, 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Corner E7: Sec. Corner 16, 17, 20 & 21, T50N, R34W:

- Hemlock post (Not found. No subsequent monuments found.)
- Aspen 10 N42E 21 (Not found. No subsequent accessories found.)
- Maple 10 S55W 24 (Not found. No subsequent accessories found.)

Corner E8: 1/4 corner between Sections 20 & 21, T50N, R34W:

- Hemlock post (Not found. No subsequent monuments found.)
- Cedar 5 N52E 8 (Not found. No subsequent accessories found.)
- Sugar 8 S55W 14 (Not found. No subsequent accessories found.)

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Corner E7: Re-established 8/28/74 on true line between original line tree stumps 12.080 ch. S and 20.291 ch. N. Found this to be a more reliable indication of where the corner was originally placed than is double proportionate measurements. Also found an original line tree stump 10.826 ch. W, the original record distance being 10.94 ch.

Corner E8: Re-established 8/29/74 on line between original line trees 27.870 ch. N and 14.082 ch. S. The corner was placed at record distance S of a 30" W. Pine L. T., rather than proportionately, on the basis of a measurement of A.B. Woods, Dep. Surveyor, in an 1854 re-measurement of the 1849 line.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Corner E7:** 1" I.D. x 36" iron pipe with 3 1/2" aluminum cap.
- Red Maple 5 S50°E (mag.) 8.0 ft. "S21, NBT"
 - Red Oak 13 N31°W (mag.) 27.5 ft. "S16, NBT"
 - Red Oak 13 N71°E (mag.) 17.3 ft. "S17, NBT"
- Corner E8:** 1" I.D. x 36" iron pipe with 3 1/2" aluminum cap.
- Sugar Maple 5 S38°E (mag.) 10.1 ft. "1/4S, NBT"
 - Red Oak 8 N42°W (mag.) 15.4 ft. "1/4S, NBT"

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE October 21, 1976

CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger

Michigan Department of Natural Resources

SURVEYOR'S MICHIGAN REGISTRATION NO. 13581

