

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>50</u> N. <u>X</u> , R. <u>34</u> W.	F7 & G8
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. _____ S., R. _____ E. _____ W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ S., R. _____ E. _____ W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Arthur O. Enger, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on Sept. 18, 1974, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:
- Corner F7:** 1/4 corner between Sections 16 & 21, T50N, R34W:
 Hemlock post (Not found. No subsequent monuments found.)
 Hemlock 20 N25W 14 (" " " " accessories ")
 Hemlock 6 S52E 20 (" " " " " ")
- Corner G8:** 1/4 corner between Sections 21 & 22, T50N, R34W:
 Ironwood post (Not found. No subsequent monuments found.)
 Y. Birch 10 N80E 22 (" " " " accessories ")
 Sugar 15 S68W 15 (" " " " " ")

- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- Corner F7:** Re-established on line between Sec. Corners 40.116 ch. to E and to W.
Corner G8: Re-established on line between Sec. Corners 39.889 ch. to N and to S.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- Corner F7:** 1" I.D. x 36" iron pipe with 3 1/2" aluminum cap.
 Red Oak 11 S 4°E (mag.) 15.9 ft. "1/4S, NBT"
 Red Oak 13 N43°E (mag.) 9.0 ft. "1/4S, NBT"
- Corner G8:** 1" I.D. x 36" iron pipe with 3 1/2" aluminum cap.
 Sugar Maple 6 N31°E (mag.) 6.8 ft. "1/4S, NBT"
 Red Maple 7 S29 1/2°W (mag.) 21.3 ft. "1/4S, NBT"

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Arthur O. Enger DATE October 25, 1976
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR

Arthur O. Enger
 Michigan Department of Natural Resources
 13581

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

