

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Baraga	Located In:	Corner Code #
(County)		
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S 30 T 50N R 34W	2
	S 18 T 50N R 34W	16
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Stephan J. Szyszkoski, in a field survey on 06/12/13 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- (2-Sec. 30) East 1/16 corner between Sections 19 and 30. Not previously monumented.
- (16-Sec. 18) East 1/16 corner between Sections 18 and 19. Not previously monumented.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (2-Sec. 30) Established the position for the corner midway and on the Section line between Section corner 1318.59' east and Quarter corner 1318.59' west.
- (16-Sec. 18) Established the position for the corner midway and on the Section line between Section corner 1328.98' east and Quarter corner 1328.98' west.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|---|---|
| <ul style="list-style-type: none"> (2) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of: 6" Oak N47°E 19.1' mrkd "1/16S BT" 5" Oak S85°E 18.7' do 5" W.Birch S24°W 10.3' do 4" Oak S89°W 9.6' do Set sq'd cedar post adjacent. E= 7877647.175 N= 215170.174 | <ul style="list-style-type: none"> (16) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of: 5" Maple N23°W 12.8' mrkd "1/16S BT" 6" Balsam N85°E 4.05' do 3" Maple S21°E 20.2' do 3" Sugar S60°W 6.1' do Set sq'd cedar post adjacent. E= 7877689.602 N= 216772.452 |
|---|---|

Bearings are magnetic. Coordinates are MCS83 in meters (NAD83(2011) Datum).
 Coord. Ref.=NGS PID DI1837: N= 221257.624 m. E= 7884435.168 m.

Signed by Stephan J. Szyszkoski Date 07/02/2013
 Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources, Forest Resources Division

