

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970 as Amended**

For corners in

Baraga	Located In:	Corner Code #
(County)		
1. Public Land Survey	T 50N R 34W	C10
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S 18 T 50N R 34W	15
	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Stephan J. Szyszkoski, in a field survey on 05/30/13 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

(C10) Quarter corner common to Sections 29 and 30. 1963 - Reestablished by Billy D. Buckler RLS midway and on line between Section corners. Set 1" iron pipe with 4" brass cap. 16" Y.Birch S44°W 16 links, 6" Maple N48°E 21 links.

(15-Sec. 18) West 1/16 corner between Sections 18 and 19. Not previously monumented.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(C10) Found the 1963 monument in good condition and at record bearing and distance from the 1963 witnesses, now rotted stumps in very poor condition. The monument is S18°W 2.1' from the proportionate position between C9 and C11 and I accept same as a careful and faithful reestablishment of the position of the original corner.

(15-Sec. 18) Established the position for the corner on the Section line between Quarter corner 1328.97' east (20.00 ch. GLO) and Section corner 1083.80' west (16.31 ch. GLO), being proportionate to the original record.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(C10) Found 1"ID I.pipe with 4" brass MI Dept. of Conservation cap. Set measuring nail with MDNR tag in the side of:  
 15" twin Maple N36°E 18.75'      mrkd "1/4S NBT"  
 14" Y.Birch S64°E 16.5'                      do  
 15" Y.Birch S06°W 39.85'                    do  
 5" Sugar N48°W 20.1'                        do  
 Set sq'd cedar post adjacent.  
 E= 7878030.870      N= 214360.433

(15) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:  
 11" Sugar N33°E 10.75'      mrkd "1/16S BT"  
 9" Sugar N84°E 1.8'                      do  
 6" Sugar S42°W 15.7'                    do  
 5" Sugar N76°W 7.3'                     do  
 Set sq'd cedar post adjacent.  
 E= 7876879.765      N= 216791.074

Bearings are magnetic. Coordinates are MCS83 in meters (NAD83(2011) Datum).  
 Coord. Ref.=NGS PID DI1837: N= 221257.624 m. E= 7884435.168 m.

Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 07/02/2013

For the Michigan Department of Natural Resources, Forest Resources Division

