

SURVEY & REMONUMENTATION

AUG 05 1994

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Baraga

(County)

Located In:

Corner Code #

1. Public Land Survey

T 50N R 34W

B-1

T _____ R _____

T _____ R _____

T _____ R _____

2. Property Controlling in Section

S _____ T _____ R _____

S _____ T _____ R _____

3. Miscellaneous

S _____ T _____ R _____

Property in Sec.

S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

RECEIVED FOR RECORD THIS 2ND DAY OF AUGUST, A.D. 1994 AT 9:00 A.M. AN RECORDED IN LIBER 4 OF LAND CORNER RECORDATION ON PAGE 500.

Theda J. Robillard

BARAGA COUNTY REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Dennis R. Destrampe, in a field survey on December 17, 1993

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:
Corner not set in original survey. No record found of being set.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
No corner evidence found. Traverse was run from standard corner at the SW corner of Section 36, T51N, R34W to standard corner at the SW corner of Section 34, T51N, R34W; corner was set by single proportionate method.



APPROVED LAND CORNER
P.A. 345 OF 1990
Baraga County

12-1-93

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 1"X36" pipe with 2½" brass cap 0.5 feet above ground. Baraga Cty Remonumentation brass cap stamped:

Witnesses:

- 7" Birch N61W 68.52' (Nail & tag "UPEA 18983" set)
- 5" Aspen S86E 101.37' (Nail & tag "UPEA 18983" set)
- Power Pole S22W 68.15' (Nail & tag "UPEA 18983" set)
- 3/4" Iron Pin West 66.64' (Nail & tag "UPEA 18983" set)

1993
T51N R34W
S.34
1/4 S.6
T50N R34W
C.C.

Signed by Dennis R. Destrampe

Date May 4, 1994

Surveyor's Michigan License No. 18983