

**SURVEY & REMONUMENTATION**

AUG 05 1994

**COMMISSION LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in  
Baraga  
(County)

Located In:

Corner Code =#

- |                                    |                           |            |
|------------------------------------|---------------------------|------------|
| 1. Public Land Survey              | T <u>50N</u> R <u>34W</u> | <u>E-1</u> |
|                                    | T _____ R _____           | _____      |
|                                    | T _____ R _____           | _____      |
|                                    | T _____ R _____           | _____      |
| 2. Property Controlling in Section | S _____ T _____ R _____   | _____      |
|                                    | S _____ T _____ R _____   | _____      |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____   | _____      |
|                                    | S _____ T _____ R _____   | _____      |

RECEIVED FOR RECORD THIS 2ND DAY OF AUGUST, A.D. 1994 AT 9:00 A.M. A.I. RECORDED IN LIBER 4 OF LAND CORNER RECORDATION ON PAGE 498.

*Hilda J. Whittard*

BARAGA COUNTY REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							

I, Dennis R. Destrampe in a field survey on December 17, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

Wood Post Original corner not found. No record found of subsequent restoration.  
 Y Birch 14 S70E 36  
 Sugar 14 S25W 51

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence found of original corner or subsequent restoration. Traverse was run from standard corner at the SW corner of Section 36, T51N, R34W to standard corner at the SW corner of Section 34, T51N, R34W; corner was set by single proportionate method.



APPROVED LAND CORNER  
 P.A. 345 OF 1990  
 Baraga County

*DR*  
12-1-93

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 1"X36" pipe with 2½" brass cap 5 inches above ground. Baraga Cty Remonumentation brass cap stamped:

Witnesses:

Power Pole N28W 91.13' (Nail & tag "UPEA 18983" set)  
 ½" Rebar West 26.49'  
 ½" Rebar East 15.51'  
 Power Pole S37W 38.24' (Nail & tag "UPEA 18983" set)

T51N R34W  
 S35  
 S5 | S4  
 T50N R34W  
 C.C.  
 1993

Signed by Dennis R. Destrampe  
 Surveyor's Michigan License No. 18983

Date May 4, 1994