

# SURVEY & REMONUMENTATION

AUG 05 1994

COMMISSION

## LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Baraga	Located In:	Corner Code #
(County)		
1. Public Land Survey	T <u>50N</u> R <u>34W</u>	I-1
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECEIVED FOR RECORD THIS 2ND DAY OF AUGUST, A.D. 1994 AT 9:00 A.M. AI RECORDED IN LIBER 4 OF LAND CORNER RECORDATION ON PAGE 494.

*Hilda J. Rohlfend*

BARAGA COUNTY REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Dennis R. Destrampe, in a field survey on December 17, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

Maple Post	Original corner not found. Corner was restored 5/6/76, recorded Liber 1, Page 270, Land Corner Recordation.
Hemlock 8 S52W 41	
Maple 5 S25E 27	

**APPROVED LAND CORNER  
P.A. 345 OF 1990  
Baraga County**

*DR*  
\_\_\_\_\_  
12-1-93

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1" iron pipe with 3 3/4" aluminum cap as described in Liber 1, Page 270, Land Corner Recordation, stamped "T50N, R34W, 3|2", A.O. Enger, RLS 13581, 5/6/76".

Witnesses found:

- 4" Red Maple S53E 9.8' PHB top & bottom
- 5" Red Maple S42W 6.3' FHB top & bottom
- 4" Red Maple N60E 7.43' Nail & disk "RLS 24591"
- 5" W. Birch N52W 25.33' Nail & disk "RLS 24591"



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner accepted as found.

Witnesses:

- |        |                |      |        |  |
|--------|----------------|------|--------|--|
| N face | 7" Sugar Maple | N15E | 34.64' | (Nail & tag "UPEA 18983" set, scribed "NBT") |
|        | 4" Red Maple   | S53E | 9.8'   | (PHB top, refreshed; PHB bottom)             |
|        | 5" Red Maple   | S42W | 6.3'   | (FHB top, refreshed; FHB bottom)             |
| W face | 6" Red Maple   | N61W | 49.72' | (Nail & tag "UPEA 18983" set, scribed "NBT") |
|        | 4" Red Maple   | N60E | 7.43'  | (Nail & disk "RLS 24591")                    |
|        | 5" W. Birch    | N52W | 25.33' | (Nail & disk "RLS 24591")                    |

Signed by Dennis R. Destrampe  
Surveyor's Michigan License No. 18983

Date June 24, 1994