

AUG 05 1994

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Baraga
 (County)

Located In: Corner Code #

- | | | |
|------------------------------------|-------------------------|-------|
| 1. Public Land Survey | T 50N R 34W | J-1 |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

RECEIVED FOR RECORD THIS 2ND DAY OF AUGUST, A.D. 1994 AT 9:00 A.M. AS RECORDED IN LIBER 4 OF LAND CORNER RECORDATION ON PAGE 493.

Della J. Robillard
 BARAGA COUNTY REGISTER OF DEEDS
 Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Dennis R. Destrampe, in a field survey on December 17, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:
 Corner not set in original survey. No record found of being set.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 No evidence of corner found. Traverse was run from the NW corner of Section 2 to the NE corner of Section 2. Corner was set at midpoint.



APPROVED LAND CORNER
 P.A. 345 OF 1990
 Baraga County

D.R.
12-1-93

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 Set 1"X36" pipe with 2½" brass cap 5" above ground. Baraga Cty. Remonumentation brass cap stamped:

Witnesses:

- S face 10" Red Maple S73E 18.68' (Nail & tag "UPEA 18983" set)
- W face 10" Y. Birch S12E 22.06' (Nail & tag "UPEA 18983" set)
- S face 9" Y. Birch N65W 11.91' (Nail & tag "UPEA 18983" set)
- W face 5" Sugar Maple N17W 15.08' (Nail & tag "UPEA 18983" set)

T51N R33W
 1/4 S2
 T50N R34W
 1994

All of the above new bearing trees are scribed "NBT".

Signed by Dennis R. Destrampe Date June 23, 1994
 Surveyor's Michigan License No. 18983