

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Baraga</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>50N</u> R <u>34W</u>	<u>J2</u>
	T _____ R _____	_____
	T _____ R _____	_____
	S _____ T _____ R _____	_____
2. Property Controlling in Section	S <u>2</u> T <u>50N</u> R <u>34W</u>	<u>11</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims

11 Oct 16 2006
 J2 Oct 11 2006

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3					●			
3									●			
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(J2) Center of Section 2. Not established in the original survey. Established by R.W.Crampton RLS circa 1988 at the intersection of straight lines connecting opposite 1/4 corners.
 (11-Sec. 2) Southwest 1/16 corner, Section 2. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(J2) Recovered Mr. Crampton's monument, a 1/2" ID iron pipe with plastic cap #24591 at the substantial intersection of 1/4 lines of Section 2. Accepted same as a careful and faithful determination of the position of the corner. Left the monument in place and made witnesses as described below.
 (11-Sec. 2) Established the corner at the intersection of straight lines connecting opposite 1/16 corners.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(J2) Found 1/2" I.pipe with plastic cap #24591. Set measuring nails in:	(11) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nails in:
15" Sugar S75E 8.6' mrkd "C1/4 BT"	19" W.Pine N24E 11.2' mrkd "1/16S BT"
10" Sugar S54W 26.7' do	6" Sugar S37E 8.0' do
7" Sugar N41W 29.6' do	5" Hemlock S24W 12.4' do
14" Sugar N04W 15.6' do	7" Hemlock N65W 13.2' do
Bearings are magnetic. Distances are to nail with tag. N18E 1.8' to steel sign post 7' tall.	Set sq'd cedar post adjacent. Bearings are magnetic. Distances are to nail with tag.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 10/24/06

For the Michigan Department of Natural Resources, Office of Land and Facilities