

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Baraga</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
	S ___ T ___ R ___	_____
2. Property Controlling in Section	S <u>2</u> T <u>50N</u> R <u>34W</u>	<u>8</u>
	S <u>2</u> T <u>50N</u> R <u>34W</u>	<u>10</u>
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims

10 Oct 10 2006
 8 Aug 30 2006

I, Stephan J. Szyszkoski, in a field survey on _____, 20__ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2							
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- (8-Sec. 2) West 1/16 corner, Section 2. Not established in the original survey. Found no subsequent record.
- (10-Sec. 2) South 1/16 corner between Sections 2 and 3. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (8-Sec. 2) Established the corner midway and on a straight line between Quarter corner (an MDNR monument) 1315.59' west and Center of Section (an iron pipe with cap #24591) 1315.59' east.
- (1-Sec. 2) Established the corner midway and on the Section line between Quarter corner 1321.90' north and Section corner 1321.90' south.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|--|--|
| (8) Set 1"IDx32" I.pipe with 4" alum.
MDNR cap. Set measuring nails in:
5" Sugar N49E 28.50' mrkd "1/16S BT"
12" Sugar S82E 23.35' do
5" Hemlock S51E 14.50' do
7" Hemlock N48W 12.90' do
Sq'd hemlock post adjacent. Bearings are magnetic. Distances are to nail with tag. | (1) Set 1"IDx32" I.pipe with 4" alum.
MDNR cap. Set measuring nails in:
14" Oak S73E 36.1' mrkd "1/16S BT"
14" twin Oak N68E 28.8' do
7" Maple S09W 0.91' do
3" Y.Birch N61W 8.25' do
Set sq'd cedar post adjacent. Bearings are magnetic. Distances are to nail with tag. |
|--|--|



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 10/24/06

For the Michigan Department of Natural Resources, Office of Land and Facilities