

SURVEY & REMONUMENTATION

MAY 17 1994

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Baraga</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>50N</u> R <u>35W</u>	<u>H-1</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

RECEIVED FOR RECORD THIS 30TH DAY OF DECEMBER A. D. 1993 AT 10:30 A. M. AND RECORDED IN LIBER 4 OF LAND CORNER RECORDATION ON PAGE 470.

Dennis R. Destrampe
 BARAGA COUNTY REGISTER OF DEEDS
 Register of Deeds Stamp & File Number

I, Dennis R. Destrampe, in a field survey on December 9, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 Corner not set in original survey.
 Corner set in U.S.F.S. survey recorded in Volume 1 of Plats, January 7, 1964.
 No L.C.R.C. was found for this corner.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 Found 2" pipe with 3" brass cap 2.2 feet above ground.
 Cap reads: T50N., R35W., C.C. 1/4 S.3, 1962 RLS 12585



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 Corner accepted as found

- Witnesses:
- 7" Maple N05E 22.01' (Nail & tag "UPEA 18983" set)
 - 12" Hemlock S60E 26.24' (Nail & tag "UPEA 18983" set)(USFS BT)
 - 10" Maple S26W 25.18' (Nail & tag "UPEA 18983" set)(USFS BT)
 - 5" Maple N66W 18.65' (8d nail found)(USFS BT)

Signed by Dennis R. Destrampe Date December 27, 1993
 Surveyor's Michigan License No. 18983