

MAY 17 1994

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Form with fields for Baraga (County), Located In: (Town/Range), Corner Code #, and numbered items 1-5 describing survey types and lot information.

RECEIVED FOR RECORD THIS 30TH DAY OF DECEMBER A. D. 1993 AT 10:30 A. M. AND RECORDED IN LIBER 4 OF LAND CORNER RECORDATION ON PAGE 468.

Signature of Arden J. Whittard, BARAGA COUNTY REGISTER OF DEEDS, Register of Deeds Stamp & File Number

I, Dennis R. Destrampe, in a field survey on December 9, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Grid table with columns A-M and rows 2-13, containing numbers 1-36. A small circle is drawn around the number 2 in row 2, column J.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration: Corner not set in original survey. Corner set in U.S.F.S. survey recorded in Volume 1 of Plats, January 7, 1964. No L.C.R.C. was found for this corner.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: Found 2" pipe with 3" brass cap 1.4 feet above ground. Cap reads: T50N, R35W, C.C., 1/4 S2, 1962 RLS 12585



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner: Corner accepted as found.

Witnesses: 8" Maple S83E 4.17' (Nail & tag "UPEA 18983" set)(USFS BT), 8" Spruce S22E 13.27' (Nail & tag "UPEA 18983" set)(USFS BT), 7" Maple S61W 4.55' (Nail & tag "UPEA 18983" set), 22" W Pine N16W 38.49' (Nail & tag "UPEA 18983" set)

Signed by [Signature of Dennis R. Destrampe] Date December 27, 1993
Surveyor's Michigan License No. 18983