

AUG 05 1994

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Baraga <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T 50N R 35W	L-1
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

RECEIVED FOR RECORD THIS 2ND DAY OF AUGUST, A.D. 1994 AT 9:00 A.M. AM RECORDED IN LIBER 4 OF LAND CORNER RECORDATION ON PAGE 491.

*Theda J. Chittell*  
 BARAGA COUNTY REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Dennis R. Destrampe, in a field survey on December 17, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							

A. Description of original monument and accessories and/or subsequent restoration:  
 Not set in original survey. No record found of corner being set.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 2½" pipe with 3" brass cap 1.5' above ground. Cap stamped T50N R35W, C.C. ½ S1, 1962, RLS 12585. Corner at midpoint of section, fits proportionate measure location.



APPROVED LAND CORNER  
 P.A. 345 OF 1990  
 Baraga County

12-1-93  
[Signature]

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner accepted as found.

- Witnesses:
- 4" Balsam N57W 13.50' (Nail & tag "UPEA 18983" set)
  - 9" Ash S60W 16.05' (Nail & tag "UPEA 18983" set)
  - 7" Ash N40E 27.32' (Nail & tag "UPEA 18983" set)
  - 9" Ash S22E 38.38' (Nail & tag "UPEA 18983" set)

Signed by Dennis R. Destrampe

Date May 17, 1994

Surveyor's Michigan License No. 18983