

APR 08 1996

COMMISSION LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Baraga (County) Located In: _____ Corner Code # _____

1. Public Land Survey T 50N R 30W C-1
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling in Section S _____ T _____ R _____
 S _____ T _____ R _____

3. Miscellaneous Property in Section S _____ T _____ R _____
 S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

RECEIVED FOR RECORD THIS 28TH DAY OF DECEMBER A.D. 1995 AT 10:30 AM AND RECORDED IN LIBER 4 OF LAND CORNER RECORDATION ON PAGES 595 - 596.

Hella J. Robillard

BARAGA COUNTY REGISTER OF DEEDS
Register of Deeds Stamp & File Number

I, Michael Mileski, in a field survey on December, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	6	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C-1; Closing Corner common to Sections 5 and 6, T50N, R30W.

See back of form

APPROVED LAND CORNER
P.A. 345 OF 1990
Baraga County
12-19-95
[Signature]

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-1; Closing Corner common to Sections 5 and 6, T50N, R30W.

A thorough search for the remains of the U.S. bearing trees was inconclusive. The search area was quite disturbed by logging operations. A search for the remains of any of the four U.S. line trees along the south line of Section 34, T51N, R30W also proved inconclusive. Reestablished this corner on line at proportionate distance between the south one-quarter corner of Section 34, T51N, R30W and the southeast corner of Section 34, T51N, R30W.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-1; Closing Corner common to Sections 5 and 6, T50N, R30W.

See back of form.



Signed by *Michael Mileski* Date 28 December 1995

Surveyor's Michigan License No. 39091 FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983

A. Description of original monument and accessories and/or subsequent restoration:

C-1; Closing Corner common to Sections 5 and 6, T50N, R30W.

Originally established during U.S. Survey conducted by Guy Carleton, D.S. in 1852 and monumented with a wood post witnessed by a

Yellow Birch 18 S45°W 80 lks. (Gone)

and a

Hemlock 26 S13°E 55 lks. (Gone)

The late Norman Thompson, RLS #4348 states in his field notes dated 28 January 1947 (copies of which were obtained from the Northern Hardwoods' office in L'Anse) that both U.S. bearing trees were "gone" and that he reestablished the corner, presumably by measurement, monumenting it with a spruce post witnessed by a

White Pine 6 S62°E 20.3'

and a

White Pine 6 S38°W 23.4'

C. Description of monument for corner and accessories established to perpetuate locating the position:

C-1; Closing Corner common to Sections 5 and 6, T50N, R30W.

Set 1" (I.D.) x 36" galvanized iron pipe with 2" aluminum cap appropriately stamped as to location.

Set 60d spike	NW/side	14" Hemlock	N50°E	39.51'
Set 60d spike	W/side	16" Sugar Maple	S22°E	41.88'
Set 60d spike	E/side	14" Red Oak	S26°W	43.45'
Set 60d spike	E/side	15" Sugar Maple	N21°W	45.38'
		1" Iron Pipe	N35°E	6.17'

All of the above new bearing trees marked with upper and lower face blazes and scribed "NBT".