

SURVEY & REMONUMENTATION

APR 26 1995

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **COMMISSION**

| | | | |
|------------------------------------------|-------------------------|---------------|-------|
| <u>Baraga</u> <small>(County)</small> | Located In: | Corner Code # | |
| | 50N 30W | E-1 | |
| 1. Public Land Survey | T _____ R _____ | _____ | _____ |
| | T _____ R _____ | _____ | _____ |
| | T _____ R _____ | _____ | _____ |
| | T _____ R _____ | _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ | _____ |
| | S _____ T _____ R _____ | _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ | _____ |
| | S _____ T _____ R _____ | _____ | _____ |

RECEIVED FOR RECORD THIS 19TH DAY OF DECEMBER, A.D. 1994 AT 9:00 A.M. AND RECORDED IN LIBER 4 OF LAND CORNER RECORDATION ON PAGES 521-522.

Richard J. Robillard
BARAGA COUNTY REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

| | | | | | | | | | | | | | |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| | A | B | C | D | E | F | G | H | I | J | K | L | M |
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | | |
| 13 | | | | | | | | | | | | | |

I, Michael Mileski, in a field survey on December 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-1; Closing Corner between Sections 4 and 5, T50N, R30W;

See back of form.

APPROVED LAND CORNER
P.A. 345 OF 1990
Baraga County

12-9-94



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-1; Closing Corner between Sections 4 and 5, T50N, R30W;

Found 1 1/4" (I.D.) x 30" iron pipe apparently knocked over by fallen maple. Set 1" (I.D.) x 36" galvanized iron pipe with 2" aluminum cap appropriately stamped as to location in accordance with recovered U.S. and Thompson bearing trees as described in Part A. Accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-1; Closing Corner between Sections 4 and 5, T50N, R30W;

Set 1" (I.D.) x 36" galvanized iron pipe with 2" aluminum cap appropriately stamped as to location.

| | | | | |
|---------------|---------|-----------------|-------|--------|
| Set 60d spike | SE/side | 15" Sugar Maple | N71°E | 18.17' |
| Set 60d spike | E/side | 13" Sugar Maple | South | 60.90' |
| Set 60d spike | E/side | 10" Sugar Maple | S44°W | 18.10' |
| Set 60d spike | NE/side | 13" Sugar Maple | N42°W | 28.75' |

All of the above new bearing trees marked with upper and lower face blazes and scribed "NBT".

Signed by Michael Mileski Date 19 December 1994

Surveyor's Michigan License No. 39091

LIBER 4 PAGE 521

A. Description of original monument and accessories and/or subsequent restoration:

E-1; Closing Corner between Sections 4 and 5, T50N, R30W;

Originally established during U.S. Survey conducted by Guy Carleton, D.S. in 1852 and monumented with a wood post witnessed by a

Sugar 20 S43°E 83lks.

(Recovered as a severely decayed stump of indeterminate size and partial fallen trunk having no identifiable marks.)

and a

Yellow Birch 12 S32°W 81lks.

(Presently alive, hollow, and 24" in dia. - Set 60d spike W/side S32°W 53.46')

The late Norman Thompson, RLS #4348, states in his field notes dated 30 January 1947 (copies of which were obtained from Northern Hardwoods' office in L'Anse) that the yellow birch U.S. bearing tree was alive and that the sugar maple U.S. bearing tree was "down". Mr. Thompson remonumented the corner with a 1" iron pipe and noted the following new bearing trees:

Sugar 7 S17°W 21.2'

(Presently alive and 11" in dia. having healed upper and lower face blazes. Set 60d spike E/side S15°W 21.20')

and a

Sugar 10 S57°E 44.2'

(Presently alive and 16" in dia. having healed upper and lower face blazes. Set 60d spike SW/side S59°E 45.20')