

A. Description of original monument and accessories and/or subsequent restoration:

G-1; Closing Corner common to Sections 3 and 4, T50N, R30W.

Originally established during U.S. Survey conducted by Guy Carleton, D.S. in 1852 and monumented with a wood post witnessed by a

Sugar Maple 18 S58°W 38 lks. (Gone)

and a

Yellow Birch 10 S31°E 41 lks. (Gone)

The late Norman Thompson, RLS #4348 states in his field notes dated 27 November 1946 (copies of which were obtained from the Northern Hardwoods' office in L'Anse) that he reestablished this corner "by measurement from the west". On 9 January 1951 Mr. Thompson set a new spruce post and recorded the following new bearing trees:

Hemlock 9 S35°E 26.7'

and a

Hemlock 13 S58°W 19.1'.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-1; Closing Corner common to Sections 3 and 4, T50N, R30W.

Set 1" (I.D.) x 36" galvanized iron pipe with 2" aluminum cap appropriately stamped as to location.

Set 60d spike	NW/side	10" Sugar Maple	N53°E	24.05'
Set 60d spike	W/side	13" Hemlock	S41°E	9.98'
Set 60d spike	E/side	12" Hemlock	S33°W	27.64'
Set 60d spike	E/side	8" Red Oak	N12°W	13.22'

All of the above new bearing trees marked with upper and lower face blazes and scribed "NBT".