

APR 08 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Baraga (County)

Located In:

Corner Code #

- 1. Public Land Survey T 50N R 31W I-1
2. Property Controlling in Section S T R
3. Miscellaneous Property in Section S T R

RECEIVED FOR RECORD THIS 28TH DAY OF DECEMBER A.D. 1995 AT 10:30 AM AND RECORDED IN LIBER 4 OF LAND CORNER RECORDATION ON PAGES 575 - 576.

Hilda G. Rhillard
BARAGA COUNTY REGISTER OF DEEDS
Register of Deeds Stamp & File Number

- 4. Lot No. , Recorded Plat
5. Private Claims

Grid table with columns A-L and rows 2-13. A dot is marked at the intersection of column I and row 2.

I, Michael Mileski, in a field survey on December, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-1; Closing Corner common to Sections 2 and 3, T50N, R31W.

APPROVED LAND CORNER
P.A. 345 OF 1990
Baraga County
12-19-95

See back of form.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-1; Closing Corner common to Sections 2 and 3, T50N, R31W.

Found a cedar post in agreement with Mr. Thompson's southwest new bearing tree and the remains of both U.S. bearing trees, the condition of each as described in Part A. Accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-1; Closing Corner common to Sections 2 and 3, T50N, R31W.

See back of form.



Signed by [Signature] Date 28 December 1995

Surveyor's Michigan License No. 39091

A. Description of original monument and accessories and/or subsequent restoration:

I-1; Closing Corner common to Sections 2 and 3, T50N, R31W.

Originally established during U.S. Survey conducted by Guy Carleton, D.S. in 1850 and monumented with a wood post witnessed by a:

Sugar 10 S60°W 19 lks.

(Recovered as a 36" tall moderately decayed stump approximately 24" in dia. slightly crushed by falling cedars having a hollow lower blaze evident with no remaining marks.)

and a

Hemlock 12 S20°E 53 lks.

(Recovered as a 36" tall severely decayed stump approximately 22" in dia. having a hollow lower blaze displaying axe marks only.)

The late Norman Thompson, R.L.S. #4348 states in his field notes dated 9 September 1947 (copies of which were obtained from the Northern Hardwoods' office in L'Anse) that both U.S. bearing trees were "ok" and that he remonumented the corner with a cedar post and established the following new bearing trees:

Sugar 2 S27°E 11.8' (Gone)

and a

Maple 9 S40°W 16.8'

(Found a 17" dia. standing dead sugar maple having a healed lower face blaze and being slightly windthrown to the southwest.

Set 60d spike S/side S38°W 17.41')

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-1; Closing Corner common to Sections 2 and 3, T50N, R31W.

Replaced found cedar post with a 1" (I.D.) x 36" galvanized iron pipe with 2" aluminum cap appropriately stamped as to location.

Set 60d spike	W/side	16" White Spruce	N17°E	36.50'
Set 60d spike	S/side	11" Balsam	N78°E	13.40'
Set 60d spike	E/side	10" Balsam	S03°W	25.32'
Set 60d spike	S/side	9" Sugar Maple	N69°W	27.62'

A control point monumented by a ½" x 18" iron rod and cap #39091 bears easterly a distance of 0.74 feet.

All of the above new bearing trees marked with upper and lower face blazes and scribed "NBT"