

APR 08 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Baraga
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 50N R 31W K-1
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Section S _____ T _____ R _____

RECEIVED FOR RECORD THIS 28TH DAY
OF DECEMBER A.D. 1995 AT 10:30 AM
AND RECORDED IN LIBER 4 OF LAND
CORNER RECORDATION ON PAGES
577 - 578.

Hilda J. Robillard

BARAGA COUNTY REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

I, Michael Mileski, in a field survey on December, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-1; Closing Corner common to Sections 1 and 2, T50N, R31W.

APPROVED LAND CORNER
P.A. 345 OF 1990
Baraga County
12-19-95

See back of form.

[Signature]

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-1; Closing Corner common to Sections 1 and 2, T50N, R31W.

Reestablished this corner on line and at proportionate distance between the south one-quarter corner of Section 32, T51N, R30W, which is an original U.S. corner, and the yellow birch U.S. line tree immediately west of the southeast corner of Section 32, T51N, R30W. This line tree was recovered by Mr. Thompson in 1945 and presently is a moderately decayed 30" tall stump approximately 26" in diameter.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-1; Closing Corner common to Sections 1 and 2, T50N, R31W.

See back of form.



Signed by *[Signature]*

Date 28 December 1995

Surveyor's Michigan License No. 39091

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983

A. Description of original monument and accessories and/or subsequent restoration:

K-1; Closing Corner common to Sections 1 and 2, T50N, R31W.

Originally established during U.S. Survey conducted by Guy Carleton, D.S. in 1852 and monumented with a wood post witnessed by a

Cedar 10 S26°W 26 lks. (Gone)

and a

Black Ash 9 S26½°E 20 lks. (Gone)

The late Norman Thompson, RLS #4348 states in his field notes dated 23 January 1947 (copies of which were obtained from the Northern Hardwoods' office in L'Anse) that he "set" this corner and monumented it with a cedar post. Mr. Thompson's notes do not indicate that any U.S. evidence was recovered nor do they indicate how he reestablished the corner. He did not record any new bearing trees. It is my feeling that Mr. Thompson reestablished this corner by measurement.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-1; Closing Corner common to Sections 1 and 2, T50N, R31W.

Set 1" (I.D.) x 36" galvanized iron pipe with 2" aluminum cap appropriately stamped as to location.

Set 60d spike	W/side	11" Black Ash	N15°E	21.12'
Set 60d spike	NE/side	12" Cedar	S45°E	26.95'
Set 60d spike	SE/side	11" Black Ash	S36°W	27.43'
Set 60d spike	S/side	15" White Spruce	S59°W	15.95'

All of the above new bearing trees are marked with upper and lower face blazes and scribed "NBT".