

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 51-42 N.R. 30 W


Benaga COUNTY

DESCRIPTION OF CORNER Section Corner for Secs. 4-5, T51N R30W and 32-33 T52N R30 W

CORNER MONUMENT 1" Iron Pipe with 4" Aluminum Cap

DATE MONUMENT PLACED AND WITNESSED 7/14/65 with Magnuson

WITNESSES TO CORNER..... 14" Cedar (S4 NBT), S 76° E, 62 $\frac{1}{2}$ Lks.



12" Cedar (S33 NBT), N 60° E, 51 Lks.

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This Corner was set from an Original BT (12" Y. Birch N 63° W, 23 Lks) which is down and has upper and lower faces. Down Cedar with axe marks (12" Cedar S 08° E, 10 Lks) and badly rotted W. Pine stump (28" W. Pine S 35° W, 23 Lks.)

SURVEYOR'S SEAL

SIGNED Frank J. Bray DATE 9/10/1965
REGISTERED LAND SURVEYOR