

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Baraga</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 51N R 30W T 51N R 30W T R	C5 E4
2. Property Controlling in Section	S T R S T R S T R	
3. Miscellaneous Property in Sec.	S T R S T R	
4. Lot No. _____, Recorded Plat		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on C5 07/24/13 and E4 07/31/13 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(C5) Corner common to Sections 7-8-17-18. 1846 - Established by Hubbard and Ives, Deputy Surveyors. Set post. Y.Birch 9" S36°E 30 links, Hemlock 10" N17°W 16 links. May 25, 1942 - Norman T. Thompson RLS notes new BTs but makes no mention of original BTs, nor of any monumentation found or set: 1) Maple 7" S05°W 18'6", 2) Maple 7" S82°E 8'2", 3) Maple 6" N73°W 18', 4) Maple 5" N19°E 16'3". Found no subsequent record.

(E4) Quarter corner common to Sections 8 and 9. 1846 - Established by Hubbard and Ives, Deputy Surveyors, midway and on the Section line between Section corners 40.00 chains north and south. Set post. Hemlock 10" S80°E 16 links, Hemlock 10" N50°W 04 links. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(C5) The original post and accessories were not recovered. Found a 1"ID iron pipe, firmly set, and the 1942 witnesses as follows: 1) no evidence; 2) found 10" Sugar with old blaze at record bearing and distance; 3) no evidence; 4) found 7" Sugar, a dead stub, with old blazes facing the pipe, at record bearing and distance. Distances from the pipe to found monuments 5319.69' north (5280' R), and 2611.58' east (2640' R) are reasonable. I accept the pipe as the best available evidence of the position of the original corner.

(E4) The original post and accessories were not recovered. Found no evidence of the position of the original corner on the ground. Reestablished the position for the corner midway and on the Section line between Section corners 2642.15' north and south.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(C5) Found 1"ID iron pipe.
 Set measuring nail with MDNR tag in the side of:
 10" Sugar S81°E 8.45' mrkd "S17 NBT" (1942 NBT)
 6" Y.Birch S33°W 26.6' mrkd "S18 NBT"
 6" Y.Birch S82°W 18.7' do
 11" Maple N63°W 3.65' " S7 NBT"
 Set sq'd cedar post adjacent.
 E= 7912243.400 N= 227329.355

(E4) Set 1"IDx32" I.pipe with 4" alum. MDNR cap.
 Set measuring nail with MDNR tag in the side of:
 4" Sugar N17°E 21.85' mrkd "1/4S NBT"
 6" Y.Birch S82°E 21.6' do
 4" Sugar S10°W 20.4' do
 4" Maple S56°W 13.7' do
 Set sq'd cedar post adjacent.
 E= 7913854.395 N= 228116.501

Bearings are magnetic. Coordinates are MCS83 in meters (NAD83(2011) Datum)
 Coord. Ref.=NGS PID D08499: N= 221257.624 m. E= 7884435.169 m.

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 10/08/2013

For the Michigan Department of Natural Resources, Forest Resources Division

