

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Baraga <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T _____ R _____ T _____ R _____ T _____ R _____	_____
2. Property Controlling in Section	S <u>6</u> T <u>51N</u> R <u>30W</u> S _____ T _____ R _____ S _____ T _____ R _____	<u>B2</u>
3. Miscellaneous Property in Sec.	S _____ T _____ R _____ S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		●		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Stephan J. Szyszkoski, in a field survey on 09/11/13 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(B2) Center of Section 6. Not previously monumented.



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(B2) Established the position for the corner at the intersection of straight lines connecting opposite 1/4 corners.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(B2) Set 1"IDx28" I.pipe with 2" alum. MDNR cap.
 Set measuring nail with MDNR tag in the side of:
 8" Cedar North 1.4' mrkd "C1/4 BT"
 8" Cedar S01°W 12.95' do
 7" Cedar S50°W 2.7' do
 4" W.Pine S61°W 11.15' do
 Set sq'd cedar post adjacent.
 E= 7911473.982 N= 229767.053

Bearings are magnetic. Coordinates are MCS83 in meters (NAD83 (2011) Datum).
 Coord. Ref.=NGS PID D08499: N= 221257.624 m. E= 7884435.169 m.

Signed by Stephan J. Szyszkoski Date 10/08/2013
 Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources, Forest Resources Division