

APR 08 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Baraga
(County)

Located in:

Corner Code #

- 1. Public Land Survey T 51N R 30W B-13
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Section S _____ T _____ R _____

RECEIVED FOR RECORD THIS 28TH DAY OF DECEMBER A.D. 1995 AT 10:30 AM AND RECORDED IN LIBER 4 OF LAND CORNER RECORDATION ON PAGES 597 - 598.

Hilda J. Robillard

BARAGA COUNTY REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Michael Mileski, in a field survey on December, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L
2	6		5		4		3		2			
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

B-13; South One-quarter Corner Section 31, T51N, R30W, on 5th Correction Line.

APPROVED LAND CORNER
P.A. 345 OF 1990
Baraga County
12-19-95
[Signature]

See back of form.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

B-13; South One-quarter Corner Section 31, T51N, R30W, on 5th Correction Line.

Found fallen cedar post. Recovered post bottom and found it to be in agreement with Mr. Thompson's northeast new bearing tree and the remains of both U.S. bearing trees, the conditions of each as described in Part A. Accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-13; South One-quarter Corner Section 31, T51N, R30W, on 5th Correction Line.

See back of form.



Signed by *Michael Mileski* Date 28 Dec 1995

Surveyor's Michigan License No. 39091

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983

A. Description of original monument and accessories and/or subsequent restoration:

B-13; South One-Quarter Corner Section 31, T51N, R30W, on 5th Correction Line.

Originally established during U.S. Survey conducted by Austin Burt, D.S. in 1845 and monumented with a wood post witnessed by a

Black Ash 11 N46°E 16 lks.

(Recovered as a 24" tall severely decayed stump approximately 22" in dia. having no visible marks. Measured N40°E 10.8' to CL from Thompson's post.)

and a

Birch 12 N59°W 40 lks.

(Recovered as an 18" tall severely decayed stump approximately 15" in dia. having no visible marks. Measured N60°W 29' to CL from Thompson's post.)

The late Norman Thompson, R.L.S. #4348 states in his field notes dated 9 May 1946 (copies of which were obtained from the Northern Hardwoods' office in L'Anse) that "the birch is down, the ash is 22, looks good, to (sic) far gone for scribing, both trees are located properly for direction and distance, set cedar post". Mr. Thompson noted the following new bearing trees:

Sugar 7 N10°E 10.6'

(Recovered as a severely decayed stump 10" in dia. together with a 15' section of fallen trunk. Trunk bears S30°W from stump. Measured N16°E 10.6' to L.)

and a

Sugar 3 N62°W 9.6' (Gone).

C. Description of monument for corner and accessories established to perpetuate locating the position of this corner.

B-13; Set 1" (I.D.) x 36" galvanized iron pipe with 2" aluminum cap appropriately stamped as to location in recovered post bottom.

Set 60d Spike	S/Side	10" Black Ash	S86°E	14.58'
Set 60d Spike	E/Side	12" Yellow Birch	S20°E	40.30'
Set 60d Spike	SE/Side	11" Balsam	S22°W	21.45'
Set 60d Spike	S/Side	26" Twin Yellow Birch	S68°W	13.62'

All of the above new bearing trees marked with upper and lower face blazes and scribed "NBT".