

SURVEY & REMONUMENTATION

APR 26 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Baraga</u> <small>(County)</small>	Located in:	Corner Code #	
	51N 30W	D-13	
1. Public Land Survey	T _____ R _____	_____	_____
	T _____ R _____	_____	_____
	T _____ R _____	_____	_____
	T _____ R _____	_____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____	_____
	S _____ T _____ R _____	_____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	_____
	S _____ T _____ R _____	_____	_____
4. Lot No. _____, Recorded Plat _____			
5. Private Claims _____			

RECEIVED FOR RECORD THIS 19TH DAY OF DECEMBER, A.D. 1994 AT 9:00 A.M. AND RECORDED IN LIBER 4 OF LAND CORNER RECORDATION ON PAGES 531-532.

Theda J. Robillard
BARAGA COUNTY REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Michael Mileski, in a field survey on December 94, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

D-13; South One-quarter Corner Section 32, T51N, R30W, on 5th Correction Line.

See back of form.

APPROVED LAND CORNER
P.A. 345 OF 1990
Baraga County
Michael Mileski
12-9-94



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-13; South One-quarter Corner Section 32, T51N, R30W, on 5th Correction Line.

Found cedar post in agreement with both of Mr. Thompson's new bearing trees the condition of each as described in Part A. Accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-13; South One-quarter Corner Section 32, T51N, R30W, on 5th Correction Line.

Replaced found cedar post with 1" (I.D.) x 36" galvanized iron pipe with 2" aluminum cap appropriately stamped as to location.

Set 60d spike	NW/side	12" Cedar	N38°E	22.17' (Thompson NBT)
Set 60d spike	S/side	10" Black Ash	N87°E	13.38'
Set 60d spike	W/side	16" Cedar	S02°E	21.54'
Set 60d spike	S/side	18" Yellow Birch	N45°W	24.27'

All of the above new bearing trees marked with upper and lower face blazes and scribed "NBT".

Signed by Michael Mileski Date 19 December 1994
Surveyor's Michigan License No. 39091

A. Description of original monument and accessories and/or subsequent restoration:

D-13; South One-quarter Corner Section 32, T51N, R30W, on 5th Correction Line.

Originally established during U.S. Survey conducted by Austin Burt, D.S. in 1845 and monumented with a wood post witnessed by a

Black Ash 16 N07°E 13 lks. (Gone)

and a

Spruce 12 N47°W 38 lks.

(Recovered as a 16" ± dia. severely decayed stump having no identifiable marks.)

The late Norman Thompson, RLS #4348, states in his field notes dated 31 July 1945 (copies of which were obtained from Northern Hardwoods' office in L'Anse) that he found both U.S. bearing trees down. Mr. Thompson remonumented the corner with a cedar post and noted the following new bearing trees:

Cedar 9 N35°E 21.7'

(Refer to Part C.)

and a

Black Ash 14 N10°W 25.7'

(Presently alive and 17" in dia. having partially healed lower face blaze with scribing evident. Set 60d spike E/side N09°W 25.70')