

APR 08 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Baraga
(County)

Located In:

Corner Code #

RECEIVED FOR RECORD THIS 28TH DAY OF DECEMBER A.D. 1995 AT 10:30 AM AND RECORDED IN LIBER 4 OF LAND CORNER RECORDATION ON PAGES 593 - 594.

- 1. Public Land Survey T 51N R 30W G-13
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Section S _____ T _____ R _____

Theda J. Robillard

BARAGA COUNTY REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	I
2	6	5	4	3	2	1						
3												
4	7	6	5	4	3	2	1					
5												
6	18	17	16	15	14	13	12	11	10	9	8	7
7												
8	19	20	21	22	23	24	25	26	27	28	29	30
9												
10	30	29	28	27	26	25	24	23	22	21	20	19
11												
12	31	32	33	34	35	36						
13												

I, Michael Mileski, in a field survey on December, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-13; Section Corner common to Sections 33 and 34, T51N, R30W, on 5th Correction Line.

See back of form.

APPROVED LAND CORNER
P.A. 345 OF 1990
Baraga County
12-19-95
[Signature]

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-13; Section Corner common to Sections 33 and 34, T51N, R30W, on 5th Correction Line.

Found cedar post in agreement with both of Mr. Thompson's new bearing trees, the condition of each as described in Part A. This post bears S15°E a distance of 1.3 feet from the face of an alive 17" dia. sugar maple having at breast height healed square blazes facing each cardinal direction. The right bank of the west branch of the Huron River is located 365 feet (U.S. = 363 feet) to the west. Accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-13; Section Corner common to Sections 33 and 34, T51N, R30W, on 5th Correction Line.

See back of form.



Signed by Michael Mileski

Date 28 Dec 1995

Surveyor's Michigan License No. 39091

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983

A. Description of original monument and accessories and/or subsequent restoration:

G-13; Section Corner common to Section 33 and 34, T51N, R30W, on 5th Correction Line.

Originally established during U.S. Survey conducted by Austin Burt, D.S. in 1845 and monumented by a 3" maple witnessed by a

Sugar 14 N67°E 24 lks. (Gone)

and a

Sugar 10 N28°W 46 lks. (Gone)

The late Norman Thompson, RLS #4348 states in his field notes dated 11 September 1946 (copies of which were obtained from the Northern Hardwoods' office in L'Anse) that he "set cor 33 & 34, no B.T., old marks and sq. sug. 10", ok from creek west branch Huron River, set cedar post". Mr. Thompson noted the following new bearing trees:

Hemlock 4 N11°E 14.1'

(Presently alive and 10" in dia. having a healed mid-trunk blaze.

Set 60d spike W/side N09°E 14.10')

and a

Yellow Birch 7 N67°W 21.3'

(Recovered as a severely decayed stump 6" tall having no visible marks.

Measured N70°W 21.6')

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.

G-13; Section Corner common to Section 33 and 34, T51N, R30W, on 5th Correction Line.

Replaced found cedar post with a 1" (I.D.) x 36" galvanized iron pipe with 2" aluminum cap appropriately stamped as to location.

Set 60d spike	NW/side	16" Sugar Maple	N55°E	39.10'
Set 60d spike	NE/side	15" Sugar Maple	S42°E	25.18'
Set 60d spike	E/side	15" Sugar Maple	S06°W	14.45'
Set 60d spike	NW/side	7" Sugar Maple	S56°W	17.43'

A control point monumented by a 1/2" x 18" iron rod and cap #39091 bears approximately S70°W a distance of 4.74 feet.

All of the above new bearing trees marked with upper and lower face blazes and scribed "NBT".