

APR 08 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Baraga
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 51N R 30W H-13
- T _____ R _____
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Section S _____ T _____ R _____

RECEIVED FOR RECORD THIS 28TH DAY
OF DECEMBER A.D. 1995 AT 10:30 AM
AND RECORDED IN LIBER 4 OF LAND
CORNER RECORDATION ON PAGES
569 - 570.

Hilda J. Robillard

BARAGA COUNTY REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

I, Michael Mileski, in a field survey on December, 1995,
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current
manual of survey instructions of the United States Department of the Interior, Bureau of Land
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and
5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a
Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found
as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

H-13; South One-quarter Corner Section 34, T51N, R30W, on 5th Correction Line.

See back of form.

APPROVED LAND CORNER
P.A. 345 OF 1990
Baraga County
12-19-95

[Signature]

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-13; South One-quarter Corner Section 34, T51N, R30W, on 5th Correction Line.

Reestablished the corner midway and on line between standard corners immediately to
the east and west. I did not recover either of Mr. Thompson's new bearing trees nor any
type of monumentation.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-13; South One-quarter Corner Section 34, T51N, R30W, on 5th Correction Line.

See back of form.



Signed by *Michael Mileski*

Date 28 Dec 1995

Surveyor's Michigan License No. 39091

A. Description of original monument and accessories and/or subsequent restoration:

H-13; South One-quarter Corner Section 34, T51N, R30W, on 5th Correction Line.

Originally established during U.S. Survey conducted by Austin Burt, D.S. in 1845 and monumented with a wood post witnessed by a

Spruce 10 N45°E 49 lks. (Gone)

and a

Birch 6 N25°W 46 lks. (Gone)

The late Norman Thompson, RLS #4348 states in his field notes dated 28 January 1947 (copies of which were obtained from the Northern Hardwoods' office in L'Anse) that he reestablished the corner according to "measurement". Mr. Thompson noted the following new bearing trees:

Sugar Maple 14 N79°W 16.3' (?)

and a

Sugar Maple 8 N47°E 45.0'.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-13; South One-quarter Corner Section 34, T51N, R30W, on 5th Correction Line.

Set 1" (I.D.) x 36" galvanized iron pipe with 2" aluminum cap appropriately stamped as to location.

Set 60d spike	S/side	8" Sugar Maple	S74°E	13.38'
Set 60d spike	NW/side	11" Sugar Maple	S34°W	23.22'
Set 60d spike	N/side	15" Sugar Maple	S68°W	51.18'
Set 60d spike	E/side	8" Sugar Maple	N16°W	24.47'

All of the new bearing trees marked with upper and lower face blazes and scribed "NBT".