

**SURVEY &
REMONUMENTATION**

APR 26 1995

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Baraga

(County)

Located In:

Corner Code #

51N 30W

L-13

- | | | | | | |
|------------------------------------|---|-------|---|-------|-------|
| 1. Public Land Survey | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| 2. Property Controlling in Section | S | _____ | T | _____ | R |
| | S | _____ | T | _____ | R |
| 3. Miscellaneous Property in Sec. | S | _____ | T | _____ | R |
| | S | _____ | T | _____ | R |

RECEIVED FOR RECORD THIS 19TH DAY OF DECEMBER, A.D. 1994 AT 9:00 A.M. AND RECORDED IN LIBER 4 OF LAND CORNER RECORDATION ON PAGES 517-518.

Theda G. Lohliand
BARAGA COUNTY REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Michael Mileski in a field survey on December 94

I, _____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

L-13; South One-quarter Corner Section 36, T51N, R30W, on 5th Correction Line.

See back of form.

APPROVED LAND CORNER
P.A. 345 OF 1990
Baraga County

[Signature]
12/9/94



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-13; South One-quarter Corner Section 36, T51N, R30W, on 5th Correction Line.

Found 1" (I.D.) x 39" iron pipe in agreement with Mr. Thompson's new bearing trees the condition of each as described in Part A. Accepted found monument as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-13; South One-quarter Corner Section 36, T51N, R30W, on 5th Correction Line.

Replaced found iron pipe with 1" (I.D.) x 36" galvanized iron pipe with 2" aluminum cap appropriately stamped as to location.

Set 60d spike	E/side	5" Red Maple	N20°E	27.65'
Set 60d spike	SW/side	18" Hemlock	S38°E	40.48'
Set 60d spike	E/side	22" Red Maple	S10°E	28.13'
Set 60d spike	NE/side	8" Sugar Maple	N79°W	54.17'

All of the above new bearing trees marked with upper and lower face blazes and scribed "NBT".

Signed by Michael Mileski Date 19 December 1994

Surveyor's Michigan License No. 39091

LIBER 4 PAGE 517

A. Description of original monument and accessories and/or subsequent restoration:

L-13; South One-quarter Corner Section 36, T51N, R30W, on 5th Correction Line.

Originally established during U.S. Survey conducted by Austin Burt, D.S. in 1845 and monumented with a wood post witnessed by a
Birch 12 N58°E 45lks. (Gone)
and a
Sugar 12 N63°W 19lks. (Gone)

The late Norman Thompson, RLS #4348, states in his field notes dated 22 November 1946 (copies of which were obtained from Northern Hardwoods' office in L'Anse) that he found the northwest (sugar maple) U.S. bearing tree to be "ok". Mr. Thompson remonumented the corner with an oak post. Per entry dated 9 January 1951, Mr. Thompson noted the following new bearing trees:

Yellow Birch 7 N08°E 8.2'
(Presently alive and 12" in diameter having healed upper and lower face blazes.
Set 60d spike W/side N06°E 8.20')

and a

Hemlock 8 S50°W 29.0'
(Presently alive and 17" in diameter having healed upper and lower face blazes.
Set 60d spike NW/side S48°W 29.00')