

**SURVEY &  
REMONUMENTATION**

APR 26 1995

**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE**

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Baraga

(County)

Located In:

51N 30W

Corner Code #

M-13

- |                                    |   |       |   |       |       |
|------------------------------------|---|-------|---|-------|-------|
| 1. Public Land Survey              | T | _____ | R | _____ | _____ |
|                                    | T | _____ | R | _____ | _____ |
|                                    | T | _____ | R | _____ | _____ |
|                                    | T | _____ | R | _____ | _____ |
| 2. Property Controlling in Section | S | _____ | T | _____ | R     |
|                                    | S | _____ | T | _____ | R     |
| 3. Miscellaneous Property in Sec.  | S | _____ | T | _____ | R     |
|                                    | S | _____ | T | _____ | R     |

RECEIVED FOR RECORD THIS 19TH DAY OF DECEMBER, A.D. 1994 AT 9:00 A.M. AND RECORDED IN LIBER 4 OF LAND CORNER RECORDATION ON PAGES 537-538.

*Theda J. Robillard*

BARAGA COUNTY REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
5. Private Claims \_\_\_\_\_

Michael Mileski

December 94

I, Michael Mileski, in a field survey on December 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

M-13; Section Corner common to Section 36, T51N, R30W, and Section 31, T51N, R29W, on 5th Correction Line.

See back of form.

APPROVED LAND CORNER  
P.A. 345 OF 1990  
Baraga County

12-9-94



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-13; Section Corner common to Section 36, T51N, R30W, and Section 31, T51N, R29W, on 5th Correction Line.

Set 1" (I.D.) x 36" galvanized iron pipe with stamped 2" aluminum cap from the northwest (sugar maple) U.S. bearing tree remains as described in Part A. A double-hack blazed line runs east and west from corner so established. Probable Thompson new bearing trees are located as follows:

- 20" live Sugar Maple with healed upper face blaze N30°W 10.9' to CL
- 10" live Hemlock with healed upper and lower face blazes N72°W 33.0' to CL

Accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-13; Section Corner common to Section 36, T51N, R30W, and Section 31, T51N, R29W, on 5th Correction Line.

Set 1" (I.D.) x 36" galvanized iron pipe with 2" aluminum cap appropriately stamped as to location.

Set 60d spike	NW/side	8" Sugar Maple	N65°E	27.03'
Set 60d spike	SW/side	13" Red Maple	S28°E	31.96'
Set 60d spike	SE/side	8" Sugar Maple	S50°W	25.95'
Set 60d spike	E/side	8" Sugar Maple	N22°W	28.15'

All of the above new bearing trees marked with upper and lower face blazes and scribed "NBT".

Signed by Michael Mileski Date 19 December 1994

Surveyor's Michigan License No. 39091

A. Description of original monument and accessories and/or subsequent restoration:

M-13; Section Corner common to Section 36, T51N, R30W, and Section 31, T51N, R29W, on 5th Correction Line.

Originally established during U.S. Survey conducted by Austin Burt, D.S. in 1845 and monumented with a wood post witnessed by a

Aspen 6 N41 ½ °E 43 lks. (Gone)

and a

Sugar 10 N30°W 36 lks.

(Recovered as a moderately decayed stump 15" ± in dia. having no identifiable marks.)

The late Norman Thompson, RLS #4348, states in his field notes dated 31 January 1950 (copies of which were obtained from Northern Hardwoods' office in L'Anse) that he recovered the northwest (sugar maple) U.S. bearing tree as a "stub" on which he "found lower". Mr. Thompson remonumented the corner with a spruce post.