

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Baraga</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T <u>51N</u> R <u>30W</u>	F1
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S <u>4</u> T <u>51N</u> R <u>30W</u>	<u>4</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims

4 Jan 19 2005
F1 Jan 05 2005

I, Stephan J. Szyszkoski, in a field survey on _____, 20____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(F1) Quarter corner common to Section 4 T51N-R30W and Section 33 T52N-R30W. 1965 - Remonumented by F.J.Bray, RLS at position of wood post "witnessed by unknown surveyor approximately 23 years ago...no original evidence found". Set 1" iron pipe with 4" aluminum cap. Witnesses to corner: 12" Hemlock S47E 37.5 links, 12" Hemlock N20E 38 links.
 (4-Sec. 4) Northwest 1/16 corner, Section 4. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(F1) Recovered the 1965 monument in good condition and at record bearing and distance from the 1965 NBTs. The Hemlock NE is in good condition, the Hemlock SE is a stump. Left the monument in place and made new witnesses as described below.
 (4-Sec. 4) Established the corner at the intersection of straight lines connecting opposite 1/16 corners.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(F1) Found 1" ID I.pipe with 4" alum. State of Michigan cap. Set measuring nails in: 14" Hemlock N25E 25.85' w/old blazes * 16" Hemlock S66W 18.5' mrkd "1/4S NBT" 11" Hemlock S67E 26.9' do 13" Cedar N05W 18.4' do Set sq'd cedar post adjacent. Bearings are magnetic. Distances are to nail with tag. * denotes 1965 NBT.	(4) Set 1" IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nails in: 7" B.Spruce N39E 2.6' mrkd "1/16S 8T" 8" B.Spruce N84E 6.9' do 8" B.Spruce S39W 7.6' do 6" W.Birch S69W 13.9' do Set sq'd cedar post adjacent. Bearings are magnetic. Distances are to nail with tag.
--	---

A	B	C	D	E	F	G	H	I	J	K	L	M
1					●							
2	6		5		4		3		2			1
3												
4	7		8		9		10		11			12
5												
6	18		17		16		15		14			13
7												
8	19		20		21		22		23			24
9												
10	30		29		28		27		26			25
11												
12	31		32		33		34		35			36
13												



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 11/22/05

For the Michigan Department of Natural Resources, Office of Land and Facilities