STATE OF MICHIGAN DEPARTMENT 0F NATURAL RESOURCES

LAND CORNER RECORD

		Baraga		COUNTY	
		т _	51N	R_	31W
DESCRIPTION OF CORNER					
CORNER MONUMENT 1" I.D. x 36" iron pipe with 4"	alumin	um ca	p.		
DATE MONUMENT PLACED AND WITNESSED August 31,	1970				
WITNESSES TO CORNER Red Maple 5 S 8°E 38.	8 ft.	"1/4	S, BT"		
Red Maple 3 N53°E 44.	2 ft.	"1/4	S, BT"		
AND	_	-			
CIRCLE CORNER REGISTERED		1			

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Corner established at intersection of quarter-section lines. East-West 1/4 line actually run between 1/4 corners. As there is no North 1/4 corner (in the water) the North-South 1/4 line was taken to be the average bearing of the east and west sides of the section.

Variation about 1000' West.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

REGISTERED LAND SURVEYOR DATE September 28, 1971

County Courthouse Area Forester (Regions I & II) District or Region Surveyor Forestry Div., Lansing

R 4047 Rev. 10/68