

STATE OF MICHIGAN  
DEPARTMENT  
OF  
NATURAL RESOURCES

LAND CORNER RECORD


Baraga COUNTY  
T 51N R 31W

DESCRIPTION OF CORNER 1/4 corner between Sections 18 & 19

CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap.

DATE MONUMENT PLACED AND WITNESSED August 31, 1970

WITNESSES TO CORNER..... Red Maple 6 N66°E (mag.) 8.5 ft. "1/4S, NBT"



Hemlock 14 N53°W (mag.) 32.7 ft. "1/4S, NBT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Corner re-established by proportionate measurement on line between an original section corner 2770.5 ft. west and a probable original section corner 2638.5 ft. east. Blazes on nearby trees indicate use of the approximate location as the corner. Found a Ford Motor Company location tag facing the corner on a tree bearing N46°W 23½ links from corner.

Variation about 1°00' West.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Arthur O. Enger  
REGISTERED LAND SURVEYOR  
Arthur O. Enger

DATE September 28, 1971

County Courthouse  
Area Forester (Regions I & II)  
District or Region Surveyor  
Forestry Div., Lansing

R 4047  
Rev. 10/68