


STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

Baraga COUNTY
T 51 N R 31 W

DESCRIPTION OF CORNER West 1/16 corner on East-West 1/4 line
CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap
DATE MONUMENT PLACED AND WITNESSED August 21, 1970
WITNESSES TO CORNER..... Cedar 8 N33°W 21.7 ft. "1/16S, BT"



Cedar 14 S71°E 40.0 ft. "1/16S, BT"
AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Not established in original survey.

Found no evidence that the corner had been previously established;
except for some blazed trees south of it evidently used for an approximate
corner.

Corner established by proportionate measurement on line between Center
1/4 corner 1329.7 ft. east and west 1/4 corner 1450.5 ft. west.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Arthur O. Enger
REGISTERED LAND SURVEYOR
Arthur O. Enger

DATE

September 28, 1971

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68