


STATE OF MICHIGAN  
DEPARTMENT  
OF  
NATURAL RESOURCES

LAND CORNER RECORD

Baraga COUNTY  
T 51 N R 31 W

DESCRIPTION OF CORNER Section Corner 17, 18, 19, and 20  
CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap.  
DATE MONUMENT PLACED AND WITNESSED August 31, 1970  
WITNESSES TO CORNER..... Sugar Maple 11 S22°W 22.0 ft. "S19, NBT"



Hemlock 18 N47°E 9.7 ft. "S17, NBT"  
Sugar Maple 15 N43°W 5.3 ft. "S18, NBT"  
AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Found a squared cedar post in place, probably set by Ford Motor Company or Celotex Corp. personnel about 1956 or 1957.

Accepted wood post as found, as it checks well with other corners around Section 18. Hemlock stump in proper position for original BT to NE, but too deteriorated to confirm except as to species. Many old blazes on nearby trees. Ford Motor Co. and Celotex Corp. location tags on nearby trees.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

*Arthur O. Eger*  
REGISTERED LAND SURVEYOR  
Arthur O. Eger

DATE

September 22, 1971

County Courthouse  
Area Forester (Regions I & II)  
District or Region Surveyor  
Forestry Div., Lansing

R 4047  
Rev. 10/68