


STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

Baraga COUNTY
T 51 N R 31 W

DESCRIPTION OF CORNER Section Corner 7, 8, 17, and 18
CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap
DATE MONUMENT PLACED AND WITNESSED September 1, 1970
WITNESSES TO CORNER..... Cedar 8 S39°E 13.3 ft. "S17, NBT"



AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Found a squared and scribed cedar post in place, as set by unknown party, with following NBT's: Cedar 9 N5°E 6.7 ft., "S7, BT" and Cedar 7 N34°E 8.5 ft., "S8, BT".

Accepted scribed post as found, as it checks reasonably well with other corners in Section 18. No trace of meander corner recorded in original notes as 3.47 ch. north of corner, but shoreline of Lake Superior appears to have changed since the original survey. Found an 8" cedar N46°E 18 ft. with Celotex Corp. location tag.

SURVEYOR'S SEAL

SIGNED

Arthur O. Enger
REGISTERED LAND SURVEYOR
Arthur O. Enger

DATE

September 23, 1971

DISTRIBUTION:

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68