

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

✓


Baraga COUNTY
T 51 N R 31-32 W

DESCRIPTION OF CORNER Section Corner 7, 12, 13 and 18

CORNER MONUMENT Witnessed 1½" I.D. iron pipe as found.

DATE MONUMENT PLACED AND WITNESSED September 1, 1970

WITNESSES TO CORNER..... Sugar Maple 5 S66½°W 34.6 ft. "S13, NBT"



W. Pine 10 N57°W 41.8 ft. "S12, NBT"

W. Birch 7 S16°E 14.0 ft. "S18, NBT"

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Found a 1½" I.D. iron pipe in place, as set by unknown party.

Accepted iron pipe as found, as it agrees substantially with other corners around Section 18. Also checks with original field note call to a "small place of bare syenitic rock on east side of high land", 1.00 ch. east of corner.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Arthur O. Enger
REGISTERED LAND SURVEYOR

DATE

September 22, 1971

Arthur O. Enger

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68