

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD


Baraga COUNTY
T 51 N R 31-32W

DESCRIPTION OF CORNER 1/4 corner between Sections 13 and 18

CORNER MONUMENT 1" I.D. x 36" iron pipe with 4" aluminum cap.

DATE MONUMENT PLACED AND WITNESSED September 1, 1970

WITNESSES TO CORNER..... Nail in power pole S70⁰E 32.15 ft.



Nail in 18" Y. Birch S86⁰W 67.45 ft.

SE corner of new bridge wing wall N13⁰E 122.9 ft.

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Corner re-established on line between original section corner 2645.1 ft. south and section corner 2645.2 ft. north. Position falls in center of N-S county road, about 25 feet south of river bank as it existed prior to re-location of the river course at this point in the late summer of 1970. Original field notes say the river was about 13 feet north of the corner.

Monument top is 6" - 8" below road surface.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Arthur O. Enger
REGISTERED LAND SURVEYOR
Arthur O. Enger

DATE

September 22, 1971

County Courthouse
Area Forester (Regions I & II)
District or Region Surveyor
Forestry Div., Lansing

R 4047
Rev. 10/68