

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Baraga</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S <u>1</u> T <u>51N</u> R <u>31W</u>	<u>9</u>
	S <u>1</u> T <u>51N</u> R <u>31W</u>	<u>L2</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Stephan J. Szyszkoski, in a field survey on 07/16/13 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- (9-Sec. 1) East 1/16 corner, Section 1. Not previously monumented.
- (L2) Center of Section 1. Not known to have been previously monumented.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (9-Sec. 1) Established the position for the corner on a straight line between Center of Section 1 1327.82' west and Quarter corner 1327.82' east.
- (L2) Established the position for the corner at the intersection of straight lines connecting opposite 1/4 corners. The position for the corner falls 3' west of the physical center of Roland Lake Road.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|--|--|
| (9) Set 1"IDx32" I.pipe with 2" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
5" Sugar N21°E 16.55' mrkd "1/16S BT"
13" Hemlock S21°E 15.85' do
4" Sugar S53°W 20.7' do
17" Cedar N59°W 27.3' do
Set sq'd cedar post adjacent.
E= 7910251.309 N= 229783.674 | (L2) Set 1"IDx32" I.pipe with 2" alum. MDNR cap 5" below the road surface. Set measuring nail with MDNR tag in the side of:
10" Sugar N59°E 66.3' mrkd "C1/4 BT"
18" Hemlock S76°E 41.5' do
9" W.Spruce S63°W 28.7' do
6" W.Spruce N19°W 59.8' do
Set sq'd cedar post adjacent.
E= 7909846.660 N= 229789.723 |
|--|--|

Bearings are magnetic. Coordinates are MCS83 in meters (NAD83(2011) Datum)
 Coord. Ref.=NGS PID D08499: N= 221257.624 m. E= 7884435.168 m.

Signed by Stephan J. Szyszkoski Date 08/15/2013
 Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources, Forest Resources Division

