

SURVEY &
REMONUMENTATION

FEB 23 1998

SECTION

A. Description of original monument and accessories and/or subsequent restoration:

C-13; Section Corner common to Sections 31 and 32, T51N, R31W, on 5th Correction Line;

Originally established during U.S. Survey conducted by Austin Burt, D.S. in 1845 and monumented with a wood post witnessed by a

Sugar 12 N60°E 09 lks.

and a

Sugar 14 N30°W 62 lks.

This corner was considered lost and reestablished midway and on line between the S¼ corner of section 31 and the S¼ corner of section 32 by Norman Thompson, P.S. #4348 on 12 November 1941. Mr. Thompson indicates in his field notes (copies of which were obtained from the Northern Hardwoods' office in L'Anse) that "the sec corner 31 & 32 was 166' (?) off, 1 corr.". Mr. Thompson does not indicate the type of monument he set, but does note the following accessories:

Sugar 7 N28°E 13'

and a

Hemlock 12 N58°W 26'