

APR 08 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Baraga
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 51N R 31W D-13
 T _____ R _____
 T _____ R _____
 T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
 Property in Section S _____ T _____ R _____
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

RECEIVED FOR RECORD THIS 28TH DAY
OF DECEMBER A.D. 1995 AT 10:30 AM
AND RECORDED IN LIBER 4 OF LAND
CORNER RECORDATION ON PAGES
601 - 602.

Nelda J. Robillard
BARAGA COUNTY REGISTER OF DEEDS
Register of Deeds Stamp & File Number

I, Michael Mileski, in a field survey on December, 1995

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

D-13; South One-quarter Corner Section 32, T51N, R31W, on 5th Correction Line.

See back of form.

APPROVED LAND CORNER
P.A. 345 OF 1990
Baraga County
12-19-95
[Signature]

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

D-13; South One-quarter Corner Section 32, T51N, R31W, on 5th Correction Line.

Found a 1½" x 44" iron pipe in reasonable agreement with both U.S. bearing tree remains the condition of which is described in Part A. Accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-13; South One-quarter Corner Section 32, T51N, R31W, on 5th Correction Line.

See back of form.



Signed by *Michael Mileski*

Date 28 Dec 1995

Surveyor's Michigan License No. 39091

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983

A. Description of original monument and accessories and/or subsequent restoration:

D-13; South One-quarter Corner Section 32, T51N, R31W, on 5th Correction Line.

Originally established during U.S. Survey conducted by Austin Burt, D.S. in 1845 and monumented with a wood post witnessed by a

Cedar 10 N61°E 20 lks.

(Recovered as a moderately decayed 18" dia. windthrown cedar stump and trunk with no remaining marks. The trunk is approximately 12' feet in length.)

and a

Birch 8 N01°W 19 lks.

(Recovered ground level yellow birch stump remains approximately 15" in dia.)

The late Norman Thompson, RLS #4348 states in his field notes probably taken in the mid 1940's (copies of which were obtained from the Northern Hardwoods' office in L'Anse) that the cedar U.S. bearing tree "looks good" and that the "old post down". Mr. Thompson set a new post and iron pipe but did not note any new bearing trees.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-13; South One-quarter Corner Section 32, T51N, R31W, on 5th Correction Line.

Replaced found iron pipe with a 1" (I.D.) x 36" galvanized iron pipe with 2" aluminum cap appropriately stamped as to location.

Set 60d spike	N/side	13" Hemlock	S75°E	17.85'
---------------	--------	-------------	-------	--------

Set 60d spike	S/side	17" Sugar Maple	S60°E	11.80'
---------------	--------	-----------------	-------	--------

(This new bearing tree has healed upper and lower face blazes and may be a Thompson NBT)

Set 60d spike	E/side	15" Hemlock	S11°E	38.32'
---------------	--------	-------------	-------	--------

Set 60d spike	S/side	8" Sugar Maple	S57°W	21.46'
---------------	--------	----------------	-------	--------

Set 60d spike	W/side	18" Yellow Birch	N09°W	28.15'
---------------	--------	------------------	-------	--------

All of the above new bearing trees except the possible Thompson NBT marked with upper and lower face blazes and scribed "NBT".