

APR 08 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Baraga  
(County)

Located In:

Corner Code #

RECEIVED FOR RECORD THIS 28TH DAY OF DECEMBER A.D. 1995 AT 10:30 AM AND RECORDED IN LIBER 4 OF LAND CORNER RECORDATION ON PAGES 603 - 604.

*Nella J. Robillard*  
BARAGA COUNTY REGISTER OF DEEDS  
Register of Deeds Stamp & File Number

1. Public Land Survey	T	<u>51N</u>	R	<u>31W</u>	<u>E-13</u>	
	T	_____	R	_____	_____	
	T	_____	R	_____	_____	
	T	_____	R	_____	_____	
2. Property Controlling in Section	S	_____	T	_____	R	_____
	S	_____	T	_____	R	_____
3. Miscellaneous Property in Section	S	_____	T	_____	R	_____
	S	_____	T	_____	R	_____

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

Michael Mileski, in a field survey on December, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L
2	6		5		4		3		2		
3											
4	7		8		9		10		11		12
5											
6	18		17		16		15		14		13
7											
8	19		20		21		22		23		24
9											
10	30		29		28		27		26		25
11											
12	31		32		33		34		35		36
13											

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
E-13; Section Corner common to Sections 32 and 33, T51N, R31W, on 5th Correction Line.

See back of form.  
APPROVED LAND CORNER  
P.A. 345 OF 1990  
Baraga County  
12-19-95  
*[Signature]*

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
E-13; Section Corner common to Sections 32 and 33, T51N, R31W, on 5th Correction Line.

Found a 1 1/2" x 30" iron pipe in agreement with the remains of the northwest U.S. bearing tree the condition of which as described in Part A.  
Accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
E-13; Section Corner common to Sections 32 and 33, T51N, R31W, on 5th Correction Line.

See back of form.



Signed by Michael Mileski Date 28 December 1995

Surveyor's Michigan License No. 39091 FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1983

## A. Description of original monument and accessories and/or subsequent restoration:

E-13; Section Corner Common to Section 32 and 33, T51N, R31W, on 5th Correction Line.

Originally established during U.S. Survey conducted by Austin Burt, D.S. in 1845 and monumented with a wood post witnessed by a

Cedar 5 N37°E 31 lks. (Gone)

and a

Cedar 12 N50°W 18 lks.

(Recovered as ground level stump remains, size indeterminate, with no marks.)

The late Norman Thompson, RLS #4348 states in his field notes probably taken in 1946 (copies of which were obtained from the Northern Hardwoods' office in L'Anse) that the northwest U.S. bearing tree was "ok" but "down". Mr. Thompson remonumented the corner with an iron pipe and post but did not note any new bearing trees.

## C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-13; Section Corner Common to Sections 32 and 33, T51N, R31W, on 5th Correction Line.

Replaced found iron pipe with a 1" (I.D.) x 36" galvanized iron pipe with 2" aluminum cap appropriately stamped as to location.

Set 60d spike	W/side	6" Black Spruce	N40°E	27.85'
Set 60d spike	S/side	13" White Birch	S62°W	19.42'

Set 60d spike	N/side	30" White Pine	N64°W	15.72'
---------------	--------	----------------	-------	--------

(This tree is a Ford Motor Company tag tree and has a partially healed upper face blaze.)

Set 60d spike	NE/side	12" Cedar	N30°W	27.73'
---------------	---------	-----------	-------	--------

All of the above new bearing trees except the white pine tag tree are marked with upper and lower face blazes and scribed "NBT".