

MAY 05 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Baraga</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>51N</u> R <u>31W</u>	<u>F-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECEIVED FOR RECORD THIS 20TH DAY OF DECEMBER, 1996 AT 10:30 A.M. AND RECORDED IN LIBER 4 OF LAND CORNER RECORDATION RECORDS ON PAGE 708.

Richard Mc Intyre
BARAGA COUNTY REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Michael Mileski, in a field survey on November, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

F-13; South One-quarter Corner Section 33, T51N, R31W, on Fifth Correction Line;

Originally established during U.S. Survey conducted by Austin Burt, D.S. in 1845 and monumented by a 16" diameter birch. No accessories were noted.

No subsequent record of this corner was found.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-13; South One-quarter Corner Section 33, T51N, R31W, on Fifth Correction Line;

This corner was considered lost and reestablished midway and on line between the standard corners immediately to the east and west. The SW corner of section 33 is an original corner and the SE corner of section 33 is probably an original corner. Corner location falls 4 feet east of the physical centerline of an unimproved, 18 foot wide, gravel road which at this point bears north and south.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-13; South One-quarter Corner Section 33, T51N, R31W, on Fifth Correction Line;

Set a 1"(I.D.) x 28" galvanized iron pipe with a 2" aluminum cap stamped as to location 12" below the road surface.

Set 7" spike	NW/side	6" White Ash	N39°E	70.77'
Set 7" spike	N/side	11" Sugar Maple	N88°E	36.85'
Set 7" spike	N/side	16" Sugar Maple	S85°W	70.90'
Set 7" spike	NE/side	8" Sugar Maple	N47°W	83.92'
		Location Post	East	15.0'

All of the above new bearing trees are marked with upper and lower blazes. The lower blaze is scribed "NBT". Both blazes as well as a band around the tree at the upper blaze are painted red.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

APPROVED LAND CORNER
P.A. 345 OF 1990
Baraga County

Mileski
12-18-96



Signed by *Michael Mileski*
Surveyor's Michigan License No. 39091

Date 18 Dec 1996