

A. Description of original monument and accessories and/or subsequent restoration:

G-13; Section Corner common to Sections 33 and 34, T51N, R31W, on 5th Correction Line.

Originally established during U.S. Survey conducted by Austin Burt, D.S. in 1845 and monumented by a 10" diameter sugar maple witnessed by a

Sugar 10 N15°W 34 lks. (Inconclusive)

The late Norman Thompson, RLS #4348 states in his field notes dated 2 December 1943 (copies of which were obtained from Northern Hardwoods' office in L'Anse) that he set a hemlock post according "to old work there is an old Sug stump looks good". What Mr. Thompson meant by "old work" is not clear. An overall examination of Mr. Thompson's field notes along the fifth correction line for Ranges 30-32 West show that considerable U.S. physical evidence was present. Furthermore, according to timber delineation maps prepared in the 1940's and 1950's and available at Mead's Peshekee Yard office in Champion this area had not yet been logged extensively. I found no other written record of subsequent restoration of this corner other than that of Mr. Thompson's. It is not unlikely therefore that Mr. Thompson's reference to "old work" related to original U.S. evidence. Mr. Thompson noted the following new bearing trees:

Hemlock 12 N20°E 11.0'
(Presently alive and 20" in dia. having healed upper and lower face blazes.)

and a

Yellow Birch 7 N66°W 23.2'
(Presently alive and 12" in dia. having healed upper and lower face blazes.)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.

G-13; Section Corner common to Sections 33 and 34, T51N, R31W, on 5th Correction Line.

Set 1" (I.D.) x 36" galvanized iron pipe with 2" aluminum cap appropriately stamped as to location as described in Part B.

| | | | | |
|---------------|---------|----------------|-------|--------|
| Set 60d spike | NW/side | 9" Sugar Maple | N52°E | 26.05' |
| Set 60d spike | SW/side | 9" Sugar Maple | S48°E | 9.45' |
| Set 60d spike | W/side | 5" Sugar Maple | S01°E | 12.70' |
| Set 60d spike | NE/side | 8" Hemlock | N42°W | 35.30' |

All of the above new bearing trees marked with upper and lower face blazes and scribed "NBT".

Mr. Thompson's new bearing trees as described in Part A were referenced as follows:

| | | | | |
|---------------|--------|------------------|-------|--------|
| Set 60d spike | E/side | 20" Hemlock | N28°E | 11.85' |
| Set 60d spike | S/side | 12" Yellow Birch | N65°W | 21.40' |