

**SURVEY &
REMONUMENTATION**

APR 26 1995

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Baraga</u> <small>(County)</small>	Located In:	Corner Code #
	51N 31W	H-13
1. Public Land Survey	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

RECEIVED FOR RECORD THIS 19TH DAY
OF DECEMBER, A.D. 1994 AT 9:00 A.M.
AND RECORDED IN LIBER 4 OF LAND
CORNER RECORDATION ON PAGES
513-514.

Robert J. Robillard
BARAGA COUNTY REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Michael Mileski, in a field survey on December 94, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

H-13; South One-quarter Corner Section 34, T51N, R31W, on 5th Correction Line.

See back of form.

APPROVED LAND CORNER
P.A. 345 OF 1990
Baraga County

[Signature]
12-9-94



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-13; South One-quarter Corner Section 34, T51N, R31W, on 5th Correction Line.

Found 3/4" (I.D.) x 35" iron pipe in agreement with Mr. Thompson's new bearing trees the condition of each as described in Part A. This monument is 30 feet west of a 3 foot wide stream (U.S. = 23.10 feet). I believe this to be a probable U.S. corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-13; South One-quarter Corner Section 34, T51N, R31W, on 5th Correction Line.

Replaced found iron pipe with a 1" (I.D.) x 36" galvanized iron pipe with 2" aluminum cap appropriately stamped as to location.

Set 60d spike	W/side	5" Sugar Maple	S11°E	25.72'
Set 60d spike	N/side	13" Sugar Maple	S81°W	36.62'
Set 60d spike	NE/side	5" Sugar Maple	N55°W	8.70'
Set 60d spike	W/side	14" Sugar Maple	N09°W	21.75'

All of the above new bearing trees marked with upper and lower face blazes and scribed "NBT".

Signed by *Michael Mileski* Date 19 December 1994

Surveyor's Michigan License No. 39091

A. Description of original monument and accessories and/or subsequent restoration:

H-13; South One-quarter Corner Section 34, T51N, R31W, on 5th Correction Line.

Originally established during U.S. Survey conducted by Austin Burt, D.S. in 1845 and monumented with a wood post witnessed by a

Birch 5 N58°E 31 lks. (Inclusive)
and a
Birch 4 N55°W 39 lks. (Inclusive)

The late Norman Thompson, RLS #4348 states in his field notes dated 2 December 1943 (copies of which were obtained from Northern Hardwoods' office in L'Anse) that he set a hemlock post according to two yellow birch stumps in all probability neither having any conclusive marks. This conclusion is based upon Mr. Thompson placing a question mark along side the U.S. bearing tree entries in his transcription of the U.S. field notes. Mr. Thompson noted the following new bearing trees:

Hemlock 10 N51°E 20.0'
(Presently alive and 16" in dia. having healed upper and lower face blazes
Set 60d spike NW/side N49°E 20.00')

and a

Sugar 6 N72°W 21.7'
(Recovered as a 36" tall solid stump 10" in dia. having healed upper and lower face blazes.)