

**SURVEY &
REMONUMENTATION**

APR 26 1995

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in **COMMISSION**
Baraga
(County)

Located In: 51N 31W Corner Code # I-13

1. Public Land Survey	T	_____	R	_____	_____
	T	_____	R	_____	_____
	T	_____	R	_____	_____
	T	_____	R	_____	_____
2. Property Controlling in Section	S	_____	T	_____	R
	S	_____	T	_____	R
3. Miscellaneous Property in Sec.	S	_____	T	_____	R
	S	_____	T	_____	R

RECEIVED FOR RECORD THIS 19TH DAY OF DECEMBER, A.D. 1994 AT 9:00 A.M. AND RECORDED IN LIBER 4 OF LAND CORNER RECORDATION ON PAGES 543-544.

Theda J. Robillard
BARAGA COUNTY REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Michael Mileski December 94

I, _____, in a field survey on _____, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-13; Section Corner common to Sections 34 and 35, T51N, R31W, on 5th Correction Line.

See back of form.

APPROVED LAND CORNER
P.A. 345 OF 1990
Baraga County

M
12-9-94



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I-13; Section Corner common to Sections 34 and 35, T51N, R31W, on 5th Correction Line.

Found 3/4" (I.D.) x 36" iron pipe and hemlock post in reasonable agreement with U.S. and Thompson bearing trees the condition of each as described in Part A. Accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

I-13; Section Corner common to Sections 34 and 35, T51N, R31W, on 5th Correction Line.

Replaced found iron pipe with 1" (I.D.) x 36" galvanized iron pipe with 2" aluminum cap appropriately stamped as to location.

Set 60d spike	E/side	10" Sugar Maple	N22°E	29.45'
Set 60d spike	NW/side	7" Red Maple	N67°E	10.80'
Set 60d spike	NE/side	13" Hemlock	S43°E	34.70'
Set 60d spike	SE/side	21" Hemlock	S42°W	44.05'

All of the above new bearing trees marked with upper and lower face blazes and scribed "NBT".

Signed by Michael Mileski Date 19 December 1994
Surveyor's Michigan License No. 39091

A. Description of original monument and accessories and/or subsequent restoration:

I-13; Section Corner common to Section 34 and 35, T51N, R31W, on 5th Correction Line.

Originally established during U.S. Survey conducted by Austin Burt, D.S. in 1845 and monumented with a wood post witnessed by a

Sugar 12 N52½°E 58 lks.

(Recovered as a 15" ± moderately decayed stump having no identifiable marks.)

and a

Sugar 8 N57°W 18 lks.

(Presently alive and 34" in dia. with the upper and lower face blazes hollowed out. Set 60d spike NE/side N62°W 11.88')

The late Norman Thompson, RLS #4348, states in his field notes dated 12 November 1943 (copies of which were obtained from Northern Hardwoods' office in L'Anse) that he found both U.S. bearing trees to be "ok". Mr. Thompson remonumented the corner with a hemlock post and noted the following new bearing tree:

Ironwood 6 N35°W 27.2'

(Presently alive and 10" in dia. having healed upper and lower face blazes. Set 60d spike NE/side N39°W 27.20')