

**SURVEY &
REMONUMENTATION**

APR 26 1995

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Baraga</u> <small>(County)</small>	Located in:	Corner Code #
	51N 31W	J-13
1. Public Land Survey	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

RECEIVED FOR RECORD THIS 19TH DAY
OF DECEMBER, A.D. 1994 AT 9:00 A.M.
AND RECORDED IN LIBER 4 OF LAND
CORNER RECORDATION ON PAGES
519-520.

Richard J. Kobillard
BARAGA COUNTY REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Michael Mileski, in a field survey on December 94, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

J-13; South One-quarter Corner Section 35, T51N, R31W, on 5th Correction Line.
See back of form.

APPROVED LAND CORNER
P.A. 345 OF 1990
Baraga County
[Signature]
2/19/94



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-13; South One-quarter Corner Section 35, T51N, R31W, on 5th Correction Line.
Found 1 1/4" (I.D.) x 36" iron pipe and cedar post from which a decayed yellow birch stump 17" in dia. having no identifiable marks is located at record U.S. bearing and distance (N42°W 39 lks = 25.74 feet). Found no evidence of the other U.S. bearing tree nor of Mr. Thompson's new bearing trees. Accepted this corner as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-13; South One-quarter Corner Section 35, T51N, R31W, on 5th Correction Line.
Replaced found iron pipe with a 1" (I.D.) x 36" galvanized iron pipe with 2" aluminum cap appropriately stamped as to location.

Set 60d spike	W/side	8" Sugar Maple	N19°E	15.78'
Set 60d spike	SW/side	13" Sugar Maple	S03°W	18.22'
Set 60d spike	S/side	14" Sugar Maple	S85°W	28.03'
Set 60d spike	SW/side	15" Hemlock	N47°W	31.75'

All of the above new bearing trees marked with upper and lower face blazes and scribed "NBT".

Signed by Michael Mileski Date 19 December 1994

Surveyor's Michigan License No. 39091

LIBER **4** PAGE **519**

A. Description of original monument and accessories and/or subsequent restoration:

J-13; South One-quarter Corner Section 35, T51N, R31W, on 5th Correction Line.

Originally established during U.S. Survey conducted by Austin Burt, D.S. in 1845 and monumented with a wood post witnessed by a

Sugar 12 N55°E 34 lks. (Gone)

and a

Birch 12 N42°W 39 lks.

(Recovered as a 17" dia. severely decayed stump having no identifiable marks.)

According to his field notes dated 12 November 1943 (copies of which were obtained at Northern Hardwoods' office in L'Anse) the late Norman Thompson, RLS # 4348 recovered the birch U.S. bearing tree and remonumented the corner with a cedar post. Mr. Thompson noted the following new bearing trees:

White Pine 9 S02°W 24.6' (Gone)

and a

Hemlock 2 S34°E 3.0' (Gone)