

**SURVEY &  
REMONUMENTATION**

APR 26 1995

**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Baraga</u> <small>(County)</small>	Located In:	Corner Code #
	<b>51N 31W</b>	<b>K-13</b>
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

RECEIVED FOR RECORD THIS 19TH DAY  
OF DECEMBER, A.D. 1994 AT 9:00 A.M.  
AND RECORDED IN LIBER 4 OF LAND  
CORNER RECORDATION ON PAGES  
515-516.

*Thelma J. Koblentz*  
BARAGA COUNTY REGISTER OF DEEDS

**Register of Deeds Stamp & File Number**

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Michael Mileski in a field survey on December 94, 19\_\_\_\_ do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

K-13; Section Corner common to Sections 35 and 36, T51N, R31W, on 5th Correction Line.

See back of form.

APPROVED LAND CORNER  
P.A. 345 OF 1990  
Baraga County

*[Signature]*  
12-9-94



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-13; Section Corner common to Sections 35 and 36, T51N, R31W, on 5th Correction Line.

Found Mr. Schmeling's 1" x 48" galvanized iron pipe with stamped 4" brass cap to be in agreement with both his and Thompson's new bearing trees the condition of each as described in Part A. I did not remonument the corner. Accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-13; Section Corner common to Sections 35 and 36, T51N, R31W, on 5th Correction Line.

Found 1" x 48" galvanized iron pipe with 4" brass cap appropriately stamped as to location.

Set 60d spike	SW/side	18" Hemlock	N33°E	57.52'
Set 60d spike	W/side	6" Black Ash	S29°E	11.23'
Set 60d spike	SE/side	14" Sugar Maple	N86°W	63.44'
Set 60d spike	S/side	6" Sugar Maple	N72°W	15.94'

All of the above new bearing trees marked with upper and lower face blazes and scribed "NBT".

Signed by *Michael Mileski* Date 19 December 1994

Surveyor's Michigan License No. 39091

A. Description of original monument and accessories and/or subsequent restoration:

K-13; Section Corner common to Sections 35 and 36, T51N, R31W, on 5th Correction Line.

Originally established during U.S. Survey conducted by Austin Burt, D.S. in 1845 and monumented with a wood post witnessed by a

Sugar 10 N27°E 75 lks.

(Recovered as a moderately decayed stump 20" in dia. having no identifiable marks.)

and a

Sugar 12 N59°W 14 lks. (Gone)

The late Norman Thompson, RLS #4348, states in his field notes dated 12 July 1945 (copies of which were obtained from Northern Hardwoods' office in L'Anse) that the northeast U.S. bearing tree was "ok". Mr. Thompson remonumented the corner with a balsam post and noted the following new bearing trees:

Hemlock 10 N54°E 18.7'

(Presently alive and 18" in dia. having healed upper and lower face blazes. Set 60d spike SE/side N53°E 18.70')

and a

Basswood 8 N21°W 15.0'

(Presently alive and 21" in dia. having healed upper blaze and hollowed out lower blaze with only ax marks evident. Set 60d spike W/side N22°W 15.00')

According to a Land Corner Recordation Certificate filed by Robert Schmeling, P.S. #8317 and recorded in Liber 1 on page 363 during the course of a field survey conducted on 24 August 1979, Mr. Schmeling recovered two scribed wood posts both down lying next to a 1" x 36" iron pipe of unknown origin in agreement with both of Mr. Thompson's new bearing trees. Mr. Schmeling replaced the found iron pipe with a 1" x 48" galvanized iron pipe with stamped 4" brass cap. Mr. Schmeling noted the following new bearing trees:

Sugar 9.0" N70°E 34.9' to CL

(Recovered as a solid stump 12" in dia. having the lower half of the lower face blaze and some scribing evident. Measured N65°E 34.9' to CL)

and a

Sugar 6.0" N43°W 40.8' to CL

(Presently alive and 8" in dia. having lower face blaze and scribing evident. Set 60d spike NE/side N47°W 40.8')