

**SURVEY &
REMONUMENTATION**

APR 26 1995

COMMISSION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Baraga</u> <small>(County)</small>	Located In:	Corner Code #
	51N 31W	L-13
1. Public Land Survey	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

RECEIVED FOR RECORD THIS 19TH DAY
OF DECEMBER, A.D. 1994 AT 9:00 A.M.
AND RECORDED IN LIBER 4 OF LAND
CORNER RECORDATION ON PAGES
533-534.

Theda J. Robillard
BARAGA COUNTY REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Michael Mileski, in a field survey on December 19 94
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the
current manual of survey instructions of the United States Department of the Interior, Bureau of Land
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5
above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a
Court of Law; established, re-established, monumented, re-monumented, recovered, found as
expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded
on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

L-13; South One-quarter Corner Section 36, T51N, R31W, on 5th Correction Line.

See back of form.

APPROVED LAND CORNER
P.A. 345 OF 1990
Baraga County
12-9-94



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-13; South One-quarter Corner Section 36, T51N, R31W, on 5th Correction Line.

Found 1" (I.D.) x 36" iron pipe in agreement with the remains of Mr. Thompson's new bearing trees
the condition of each is described in Part A. From this monument a badly decayed sugar maple
stump is located at record U.S. bearing and distance (N39°W 41 lks = 27.06 feet). Accepted as a
careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-13; South One-quarter Corner Section 36, T51N, R31W, on 5th Correction Line.

Replaced found iron pipe with 1" (I.D.) x 36" galvanized iron pipe with 2" aluminum cap appropriately
stamped as to location.

Set 60d spike	NW/side	13" White Spruce	N11°E	29.33'
Set 60d spike	S/side	12" Sugar Maple	S40°W	27.03'
Set 60d spike	SW/side	5" Sugar Maple	N88°W	8.19'
Set 60d spike	E/side	12" Sugar Maple	S62°W	18.32'

All of the above new bearing trees marked with upper and lower face blazes and scribed "NBT".

Signed by Michael Mileski Date 19 December 1994

Surveyor's Michigan License No. 39091

LIBER 4 PAGE 533

A. Description of original monument and accessories and/or subsequent restoration:

L-13; South One-quarter Corner Section 36, T51N, R31W, on 5th Correction Line.

Originally established during U.S. Survey conducted by Austin Burt, D.S. in 1845 and monumented with a wood post witnessed by a

Sugar 12 N69°E 61 lks. (Gone)

and a

Sugar 6 N39°W 41 lks.

(Recovered as an 18" dia. severely decayed stump 30" tall having no identifiable marks.)

The late Norman Thompson, RLS #4348, states in his field notes dated 24 July 1945 (copies of which were obtained from Northern Hardwoods' office in L'Anse) that he found a U.S. bearing tree but does not identify which one. Mr. Thompson remonumented the corner with a balsam post and noted the following new bearing trees:

Sugar 11 N03°E 21.4'

(Recovered as a 15" stump having no marks.)

and a

Sugar 14 N86°W 32.0'

(Recovered as a windthrown stump, size indeterminate, and with no marks.)