

APR 08 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Baraga
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 51N R 32W C-13
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Section S _____ T _____ R _____

RECEIVED FOR RECORD THIS 28TH DAY OF DECEMBER A.D. 1995 AT 10:30 AM AND RECORDED IN LIBER 4 OF LAND CORNER RECORDATION ON PAGES 617 - 618.

Hilda J. Robillard

BARAGA COUNTY REGISTER OF DEEDS

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Michael Mileski, in a field survey on December, 19 95

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C-13; Section Corner common to Sections 31 and 32, T51N, R32W, on 5th Correction Line.

APPROVED LAND CORNER
P.A. 345 OF 1990
Baraga County
12-19-95
[Signature]

See back of form.

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	8	9	10	11	12					
5											
6	18	17	16	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-13; Section Corner common to Sections 31 and 32, T51N, R32W, on 5th Correction Line.

Found a 12" dia. aspen having open mid-trunk blazes facing each cardinal direction and scribed "SC" in reasonable agreement with recovered U.S. bearing tree the condition of which is described in Part A. Accepted as a careful and faithful perpetuation of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-13; Section Corner common to Sections 31 and 32, T51N, R32W, on 5th Correction Line.

See back of form.



Signed by Michael Mileski

Date 28 Dec 1995

Surveyor's Michigan License No. 39091

A. Description of original monument and accessories and/or subsequent restoration:

C-13; Section Corner common to Sections 31 and 32, T51N, R32W, on 5th Correction Line.

Originally established during U.S. Survey conducted by Austin Burt, D.S. in 1845 and monumented with a wood post witnessed by a

Cedar 7 N23°E 11 lks.

(Recovered as a stump hole and fallen trunk with no marks.)

and a

Cedar 10 N62°W 20 lks. (Gone)

This corner was reestablished from the remains of both U.S. bearing trees by Stephen Douglas of the Bureau of Land Management during the course of a survey conducted from 27 May 1985 to 30 September 1986 and approved 17 February 1989. Mr. Douglas states in his notes that the corner was not monumented.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-13; Section Corner common to Sections 31 and 32, T51N, R32W, on 5th Correction Line.

Set a 1" (I.D.) x 36" galvanized iron pipe with 2" aluminum cap appropriately stamped as to location underneath a BLM stake and tack found on the south side of the 12" aspen described in Part B.

Set 60d spike	W/side	10" Red Maple	S21°E	20.97'
Set 60d spike	S/side	6" Red Maple	S48°W	28.00'
Set 60d spike	SW/side	5" White Spruce	N36°W	17.98'
Set 60d spike	S/side	6" Red Maple	S62°E	38.46'

All of the above new bearing trees marked with upper and lower face blazes and scribed "NBT".