

SURVEY &  
REMONUMENTATION

APR 26 1995

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Baraga</u> <small>(County)</small>	Located in:	Corner Code #
	51N 32W	E-13
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

RECEIVED FOR RECORD THIS 19TH DAY  
OF DECEMBER, A.D. 1994 AT 9:00 A.M.  
AND RECORDED IN LIBER 4 OF LAND  
CORNER RECORDATION ON PAGES  
535-536.

*Theda J. Robillard*  
BARAGA COUNTY REGISTER OF DEEDS

Register of Deeds Stamp & File Number

Michael Mileski in a field survey on December 94, 19 \_\_\_\_\_

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

E-13; Section Corner common to Sections 32 and 33, T51N, R32W, on 5th Correction Line.

See back of form.

APPROVED LAND CORNER  
P.A. 345 OF 1990  
Baraga County  
*[Signature]*  
12-9-94



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-13; Section Corner common to Sections 32 and 33, T51N, R32W, on 5th Correction Line.

Found 2 1/2" x 30" aluminum pipe with stamped 3" cap along side of a 1 3/4" iron pipe in agreement with the BLM new bearing trees. This monument was accepted as a careful and faithful perpetuation of the position of the original corner by the BLM.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-13; Section Corner common to Sections 32 and 33, T51N, R32W, on 5th Correction Line.

Found 2 1/2" x 30" aluminum pipe with 3" cap appropriately stamped as to location.

Set 60d spike	NE/side	8" Jack Pine	N58°E	29.55'
Set 60d spike	SW/side	8" Jack Pine	S43°E	21.22'
Set 60d spike	SE/side	20" Red Pine	S54°W	31.48'
Set 60d spike	E/side	6" Red Pine	N07°W	29.90'

All of the above new bearing trees marked with upper and lower face blazes and scribed "NBT".

Signed by *Michael Mileski* Date 19 December 1994

Surveyor's Michigan License No. 39091

A. Description of original monument and accessories and/or subsequent restoration:

E-13; Section Corner common to Sections 32 and 33, T51N, R32W, on 5th Correction Line.

Originally established during U.S. Survey conducted by Austin Burt, D.S. in 1845 and monumented with a wood post witnessed by a

Yellow Pine N62°E 10 lks.

(Inconclusive - No diameter is given in the U.S. field notes.)

and a

Yellow Pine N07½°W 17 lks.

(Inconclusive - No diameter is given in the U.S. field notes.)

During the course of a survey conducted by Michael Avery and Stephen Douglas of the Bureau of Land Management from 17 September 1982 to 30 September 1983 and approved 8 July 1985, this corner was found to be monumented with a 1 3/4" iron pipe "lying along side of which is the decayed remains of a wooden post with no mks. visible". The BLM field notes for this survey states that each U.S. bearing tree was recovered a "decayed and charred pine stump" in reasonable agreement with the U.S. record. This corner was remonumented with a 2½" x 30" aluminum pipe with stamped 3" cap during the course of a survey conducted by Stephen Douglas of the BLM from 27 May 1985 to 30 September 1986 and approved 17 February 1989. The following new bearing trees were noted by the BLM:

Jack Pine 11 N28°E 54 lks.

and a

Jack Pine 12 N44°W 43 lks.