

APR 08 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Baraga (County) Located In: Corner Code #
1. Public Land Survey T 51N R 32W G-13
2. Property Controlling in Section S T R
3. Miscellaneous Property in Section S T R

RECEIVED FOR RECORD THIS 28TH DAY OF DECEMBER A.D. 1995 AT 10:30 AM AND RECORDED IN LIBER 4 OF LAND CORNER RECORDATION ON PAGES 611 - 612.

Handwritten signature of the Register of Deeds.

BARAGA COUNTY REGISTER OF DEEDS
Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

Grid table with columns A-L and rows 2-13. A small black square is marked at the intersection of column G and row 13.

I, Michael Mileski, in a field survey on December, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
G-13; Section Corner common to Sections 33 and 34, T51N, R32W, on 5th Correction Line.

See back of form.

APPROVED LAND CORNER
P.A. 345 OF 1990
Baraga County
12-19-95
[Signature]

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
G-13; Section Corner common to Sections 33 and 34, T51N, R32W, on 5th Correction Line.

Reestablished corner position at position indicated in Part A.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
G-13; Section Corner common to Sections 33 and 34, T51N, R32W, on 5th Correction Line.

See back of form.



Signed by [Signature] Date 28 December 1995

Surveyor's Michigan License No. 39091 FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971 REVISED MAY 14, 1975 REVISED JAN., 1983

A. Description of original monument and accessories and/or subsequent restoration:

G-13; Section Corner common to Sections 33 and 34, T51N, R32W, on 5th Correction Line.

Originally established during U.S. Survey conducted by Austin Burt, D.S. in 1845 and monumented with a wood post witnessed by a

Cedar 6 N41°E 17 lks. (Gone)

and a

Spruce 12 N22°W 25 lks. (Gone)

This corner was reestablished at proportionate distance between the southwest corner of Section 33, T51N, R32W and the southeast corner of Section 34, T51N, R32W by Michael Avery and Stephen Douglas of the Bureau of Land Management from 17 September 1982 to 30 September 1983 and approved 8 July 1985. Mr. Avery and Mr. Douglas did not remonument the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-13; Section Corner common to Sections 33 and 34, T51N, R32W, on 5th Correction Line.

Set 1" (I.D.) x 36" galvanized iron pipe with 2" aluminum cap appropriately stamped as to location.

Set 60d spike	S/side	4" White Pine	N78°E	10.88'
Set 60d spike	E/side	4" White Pine	S47°E	27.61'
Set 60d spike	W/side	4" White Pine	S28°W	12.79'
Set 60d spike	N/side	4" White Pine	S89°W	22.37'

All of the above new bearing trees marked with upper and lower face blazes and scribed "NBT".